

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02418

Company- STANOLIND OIL & GAS CO.
Farm- Ruth L. Zeigler No. 2

SEC. 26 T. 10 R. 21W
SW NE SW

Total Depth. 3779'
Comm. 10-13-56 Comp. 10-30-56
Shot or Treated.
Contractor.
Issued. 11-24-56

County Graham
KANSAS



Elevation. 2148' Gr.

CASING:

8 5/8" 220' w/150 sx csm.

Production. Dry

Figures indicate Bottom of Formations.

clay	30
gravel	40
sand-shale	180
shale	800
shale-sand strks	1020
shale	1390
red bed	1612
Anhydrite	1655
shale	1715
shale-shells	2000
shale	2015
shale-shells	2265
lime-shale	3325
lime	3629
lime-shale	3750
lime-shale-chert	3757
lime	3779
Total Depth	

TOPS:

Heebner	3388
Lansing	3429
Arbuckle	3746

DST #1 - 3736-52' Misrum.

DST #2 - 3711-56' Open 1 hr.,
Rec. 2' mud w/specks of oil.
IBHP 40#, FBHP 0. SIBHP 170# in
20 min.

DST #3 - Open 1 hr., rec. 780'
wbr., no show. IBHP 1162.
IFBHP 55. FFBHP 385. SIBHP 1150
in 20 min.