

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-005-01816

Company- CITIES SERVICE OIL CO.  
Farm- Fondoble No. 8

SEC. 36 T. 10 R. 21W  
NE SW SE  
990' N & 990' E of S/4 Cor.

Total Depth. 3743'

Comm. 1-1-56 Comp. 1-17-56


Shot or Treated. 500 gals. acid 1-18-56

Contractor. Lohmann-Johnson Drlg. Co., Inc.

Issued. 3-10-56

County Graham

KANSAS



Elevation. 2137' Gr.

Production. 174 BO, NW, 24 hrs.

CASING:

8 5/8" 240' cem w/175 sx

5 1/2" 3723' cem w/150 sx

Figures Indicate Bottom of Formations.

sand & shale	240
shale	935
sand & red bed	1585
anhydrite	1610
shale, shells & lime	2000
shale & lime	2445
lime & shale	2870
lime	3725
lime & shale	3728
3728 RTD = 3725 SLM	
lime	3743
Total Depth	
Tops: Corr.	
Topeka	3166
Heebner	3374
Dodge	3398
Lansing	3412
Conglomerate	3659
Eros. Simpson	3704
Arbuckle	3722
Penetration	21'