

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-03042

Company- HARRY GORE
Farm- C. V. Lewis

No. 6

SEC. 36 T. 10 R. 23W
SE SE NW

Total Depth. 3746

Comm. 1-7-55


Comp. 1-19-55

Shot or Treated.

Contractor. Veeder Supply & Development Co.

Issued. 3-12-55

County Graham
KANSAS



CASING:

8 5/8" 190' cem. w/125 sx
5 1/2" 3594' cem. w/100 sx

Elevation. 2100 KB

Production. 97 bbls. oil

Figures indicate Bottom of Formations.

sand, gravel & shale	70
gravel, yellow shale	110
blue shale	190
shale & shells	720
sand	785
shale & shells	1000
sand & shale	1300
shale & shells	1400
shale & redbed	1542
Anhydrite	1591
shale & shells	2160
shale & lime streaks	2320
lime & shale	2785
shale & lime shells	2875
shale & lime	3295
lime	3680
cherty lime	3701
Conglomerate	3746
Total depth	

Tops:

Topeka	3133
Heebner	3339
Toronto	3365
Lansing-KC	3382
Base KC	3607
Cherty Congl.	3656
No Arbuckle	