

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01823

Company- HERMAN GEORGE KAISER
Farm- Schneider "A" No. 8

SEC. 36 T. 10 R. 21W
NE NE SW

Total Depth. 3702

Comm. 1-30-55

Comp. 2-11-55


Shot or Treated.

Contractor. H-30, Inc.

Issued. 1-14-56

County Graham

KANSAS



CASING:
8 5/8 192'
5 1/2 3696'

Elevation. 2101 KB

Production. 90 BOPD

Figures indicate Bottom of Formations.

surface clay & sand	80
shale	625
shale, shells & iron	1080 ✓
sand	1250
shale, shells & red bed	1545
anhydrite	1595
shale; shells & red bed	2175
shale, lime & salt	2220
shale & lime	3702
Total Depth	

TOPS:	
Heebner	3338
Toronto	3360
Lansing	3379
Base K. C.	3608
Conglomerate	3650
Arbuckle	3691

DST #1: 3498-3560, open 1 hr. rec.
30' SOC, BHP 0#/15 min.

DST #2: 3562-3600, open 40 min. rec.
40' mud w/ slight oil specks, BHP
130#/15 min.

DST #3: 3692-96, open 40 min. rec.
13' mud, no shows, BHP 510#/15 min.

DST #4: 3696-3702, open 1 hr. rec.
60' HOCM, 30' free oil, BHP 396#/15 min.

bailer test 1/2 to 3/4 BOPH, 1000gal.
acid MP 1100# treated @ 1100#
swb. 1 1/2 BOPH, NW 3000 gal acid. MP
1000# @ rate 20 bbl acid per min.
no break. Swb. 4 BOPH, 10% wtr.