15-065-23324

American Warrior Inc

Webster #1-26

26 10 22 Graham KS

DST # 1

LKC-"A-D"

2007.08.22

TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc**

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

26 10 22 Graham KS

Webster #1-26

Start Date: 2007.08.22 @ 23:46:24
End Date: 2007.08.23 @ 19:01:24
Job Ticket #: 28882 DST #: 1

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 24 2007
CONSERVATION DIVISION
WICHITA, KS

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

DRILL STEM TEST REPORT

TRILOBITE TESTING, INC

American Warrior Inc

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

Webster #1-26

26 10 22 Graham KS

Job Ticket: 28882 **DST#: 1**

Test Start: 2007.08.22 @ 23:46:24

GENERAL INFORMATION:

Formation: **LKC-"A-D"**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 14:44:54
Time Test Ended: 19:01:24

Test Type: Conventional Bottom Hole
Tester: Jason McLemore
Unit No: 32

Interval: 3541.00 ft (KB) To 3615.00 ft (KB) (TVD)
Total Depth: 3615.00 ft (KB) (TVD)
Hole Diameter: 7.80 inches Hole Condition: Good


Reference Elevations: 2280.00 ft (KB)
2272.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 6719 **Inside**

Press@RunDepth: 203.75 psig @ 3544.00 ft (KB)
Start Date: 2007.08.22 End Date: 2007.08.22
Start Time: 12:46:26 End Time: 19:01:24

Capacity: 7000.00 psig
Last Calib.: 2007.08.23
Time On Btm: 2007.08.22 @ 14:44:24
Time Off Btm: 2007.08.22 @ 17:14:54

TEST COMMENT: IFP Fair Blow BOB in 12 Min.
ISI Dead
FFP Fair Blow BOB in 22 Min.
FSI Dead



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1695.99	105.76	Initial Hydro-static
1	17.57	105.48	Open To Flow(1)
31	110.02	107.65	Shut-In(1)
63	425.85	109.35	End Shut-In(1)
63	112.70	109.27	Open To Flow(2)
106	203.75	110.93	Shut-In(2)
150	420.08	111.59	End Shut-In(2)
151	1639.87	112.00	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
390.00	SMW 90%W 10%M	5.47

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

Webster #1-26

26 10 22 Graham KS

Job Ticket: 28882 **DST#: 1**

Test Start: 2007.08.22 @ 23:46:24

Tool Information

Drill Pipe:	Length:	3552.00 ft	Diameter:	3.80 inches	Volume:	49.83 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	2.70 inches	Volume:	0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight to Pull Loose:	60000.00 lb
					Total Volume:	49.83 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:		32.00 ft					String Weight: Initial	54000.00 lb
Depth to Top Packer:		3541.00 ft					Final	58000.00 lb
Depth to Bottom Packer:		ft						
Interval between Packers:		74.00 ft						
Tool Length:		95.00 ft						
Number of Packers:		2	Diameter:	6.75 inches				

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			3521.00		
Shut In Tool	5.00			3526.00		
Hydraulic tool	5.00			3531.00		
Packer	5.00			3536.00	21.00	Bottom Of Top Packer
Packer	5.00			3541.00		
Stubb	1.00			3542.00		
Perforations	1.00			3543.00		
Change Over Sub	1.00			3544.00		
Recorder	0.00	6719	Inside	3544.00		
Blank Spacing	62.00			3606.00		
Change Over Sub	1.00			3607.00		
Perforations	5.00			3612.00		
Recorder	0.00	13221	Outside	3612.00		
Bullnose	3.00			3615.00	74.00	Bottom Packers & Anchor
Total Tool Length:	**95.00**					

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

Webster #1-26

26 10 22 Graham KS

Job Ticket: 28882 **DST#: 1**

Test Start: 2007.08.22 @ 23:46:24

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	14000 ppm
Viscosity:	44.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	8.99 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	1800.00 ppm				
Filter Cake:	inches				


Recovery Information


Recovery Table

Length ft	Description	Volume bbl
390.00	SMW 90%W 10%M	5.471

Total Length: 390.00 ft Total Volume: 5.471 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:
Laboratory Name: Laboratory Location:
Recovery Comments:


Pressure vs. Time
6719 Pressure
6719 Temperature
Initial Hydro-static
Final Hydro-static
End Shut-In(1)
End Shut-In(2)
Shut-In(1)
Shut-In(2)
Open To Flow(1)
Open To Flow(2)
Pressure
Temperature
1750
1500
1250
1000
750
500
250
-0
110
105
100
95
90
85
80
75
70
3PM
6PM
22 Wed Aug 2007
Time (Hours)



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc**

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

26 10 22 Graham KS

Webster #1-26

Start Date: 2007.08.24 @ 02:00:43
End Date: 2007.08.24 @ 07:05:43
Job Ticket #: 28883 DST #: 2

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

DRILL STEM TEST REPORT

TRILOBITE TESTING, INC

American Warrior Inc

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

Webster #1-26

26 10 22 Graham KS

Job Ticket: 28883 **DST#: 2**

Test Start: 2007.08.24 @ 02:00:43

GENERAL INFORMATION:

Formation: **LKC-"H-K"**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 03:27:43
Time Test Ended: 07:05:43

Test Type: Conventional Bottom Hole
Tester: Jason McLemore
Unit No: 32

Interval: 3668.00 ft (KB) To 3760.00 ft (KB) (TVD)
Total Depth: 3760.00 ft (KB) (TVD)
Hole Diameter: 7.80 inches Hole Condition: Good


Reference Elevations: 2280.00 ft (KB)
2272.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 6719 **Inside**

Press@RunDepth: 15.67 psig @ 3671.00 ft (KB)
Start Date: 2007.08.24 End Date: 2007.08.24
Start Time: 02:00:45 End Time: 07:05:43

Capacity: 7000.00 psig
Last Calib.: 2007.08.24
Time On Btm: 2007.08.24 @ 03:27:13
Time Off Btm: 2007.08.24 @ 05:28:43

TEST COMMENT: IFP Weak Blow Built to 1 "
ISI Dead
FFP Dead
FSI Dead



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1795.50	107.96	Initial Hydro-static
1	13.54	107.65	Open To Flow (1)
32	16.21	108.78	Shut-In(1)
61	72.95	109.50	End Shut-In(1)
61	15.69	109.49	Open To Flow (2)
93	15.67	110.11	Shut-In(2)
121	35.14	110.60	End Shut-In(2)
122	1776.37	111.15	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
7.00	Mud w/Oil Specks	0.10

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

Webster #1-26

26 10 22 Graham KS

Job Ticket: 28883 **DST#: 2**

Test Start: 2007.08.24 @ 02:00:43

Tool Information

Drill Pipe:	Length:	3676.00 ft	Diameter:	3.80 inches	Volume:	51.56 bbl	Tool Weight:		2000.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	2.70 inches	Volume:	0.00 bbl	Weight set on Packer:		25000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight to Pull Loose:		65000.00 lb
					Total Volume:	51.56 bbl	Tool Chased		0.00 ft
Drill Pipe Above KB:		29.00 ft					String Weight:	Initial	62000.00 lb
Depth to Top Packer:		3668.00 ft						Final	62000.00 lb
Depth to Bottom Packer:		ft							
Interval betw een Packers:		92.00 ft							
Tool Length:		113.00 ft							
Number of Packers:		2	Diameter:	6.75 inches					

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Change Over Sub	1.00			3648.00		
Shut In Tool	5.00			3653.00		
Hydraulic tool	5.00			3658.00		
Packer	5.00			3663.00	21.00	Bottom Of Top Packer
Packer	5.00			3668.00		
Stubb	1.00			3669.00		
Perforations	1.00			3670.00		
Change Over Sub	1.00			3671.00		
Recorder	0.00	6719	Inside	3671.00		
Blank Spacing	62.00			3733.00		
Change Over Sub	1.00			3734.00		
Perforations	23.00			3757.00		
Recorder	0.00	13221	Outside	3757.00		
Bullnose	3.00			3760.00	92.00	Bottom Packers & Anchor
Total Tool Length:	**113.00**					

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc

PO Box 399
Garden City KS 67846

ATTN: Jason Alm

Webster #1-26

26 10 22 Graham KS

Job Ticket: 28883 **DST#: 2**

Test Start: 2007.08.24 @ 02:00:43

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	53.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	8.99 in³	Gas Cushion Type:			
Resistivity:	ohm.m	Gas Cushion Pressure:	psig		
Salinity:	2000.00 ppm				
Filter Cake:	inches				

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
7.00	Mud w/Oil Specks	0.098

Total Length: 7.00 ft Total Volume: 0.098 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:

Laboratory Name: Laboratory Location:

Recovery Comments:



Pressure vs. Time
6719 Pressure
6719 Temperature
Initial Hydro-static
Final Hydro-static
Open To Flow(1)
Shut-In(1)
End Shut-In(1)
Open To Flow(2)
Shut-In(2)
End Shut-In(2)
Pressure
Temperature
1750
1500
1250
1000
750
500
250
0
110
105
100
95
90
85
80
75
70
65
2AM
3AM
4AM
5AM
6AM
7AM
24 Fri Aug 2007
Time (Hours)

CHART PAGE

This is a photocopy of the actual AK-1 recorder chart

