Initial Closed In Time	20 Minutes		
Tool Open Flow Period	90 Minutes		
Final Closed In Time	20 Minutes		

Depth Top Gauge	3735 Ft.	Blanked Off	no
BT. P.R.D. No	700	12 Hr. Clock	
Pressure Readings	Field	Office Corrected	
Initial Hydro Mud Pressure	2040	2086	
Initial Closed in Pres.	150	130	
Initial Flow Pres.	40	34	
Final Flow Pres.	100	99	
Final Closed in Pres.	640	644	
Final Hydro Mud Pressure	2040	2074	

Depth Center Gauge	- Ft.	Blanked Off	yes
BT. P.R.D. No	1728	12 Hr. Clock	
Pressure Readings	Field	Office Corrected	
Initial Hydro Mud Pressure			
Initial Closed in Pres.			
Initial Flow Pres.			
Final Flow Pres.			
Final Closed in Pres.			
Final Hydro Mud Pressure			

Depth Bottom Gauge	Ft.	Blanked Off	
BT. P.R.D. No		Hr. Clock	
Pressure Readings	Field	Office Corrected	
Initial Hydro Mud Pressure			
Initial Closed in Pres.			
Initial Flow Pres.			
Final Flow Pres.			
Final Closed in Pres.			
Final Hydro Mud Pressure			

Amount-Type of Cushion	none

Date	4-8-58
Ticket No.	164299
HOWCO DISTRICT	Hill City
Kind of Job	Open Hole

CONTRACTOR RIG #2

HOLE & TOOL DATA

Elevation	2330'	Top Packer Depth	3724'
Total Depth	3770	Bottom Packer Depth	3729
Casing or Hole Size	7 7/8"	Size & Type Wall Packer	(2) 6 3/4" E.S. W.P.
Liner or Rathole Size	7 7/8"	Size Bottom Choke	5/8"
Casing Perforations	Top / Bottom	Size Surface Choke	1"
Interval Tested	3729-3770'	ID & Length Air Chamber	3.8 x 30'
Formation Tested	Kansas City	ID & Length Drill Collars	-
Est. Gauge Depth Temp.	Actual 97 F°	Size Drill Pipe	4½" API FH
MUD DATA Weight	10.4	Viscosity	41
All depths measured from	Kelly Bushing	No. Folders Reproduced	2

REMARKS: Set packer, opened tool and took a 20 Minute Initial closed in pressure.(11:42-12:02 AM) Opened tool with a fair blow of air throughout test. Closed tool at 1:32 A Off bottom at 1:53 P.M. NO SPECIAL READING DUE TO CHARACTER OF TEST.

Recovered	90	Feet of	gas
Recovered	50	Feet of	oil cut mud
Recovered	30	Feet of	heavily oil cut mud
Recovered	50	Feet of	very heavily oil cut mud

Witnessed By Wayne Brinegar

Tester N.N. Dreiling

LOCATION 2-10-22

HOLMS — LEASE NAME

1 — WELL NO.

2 — TEST NO.


FIELD WILDCAT

COUNTY GRAHAM

STATE KANSAS


K AND E DRILLING INC. — LEASE OWNER

GREAT BEND — OWNERS DISTRICT



PRESSURE

TIME



Each horizontal Line Equal to 1000 p.s.i.