

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-00991


Company- DAVIS BROTHERS
Farm- Sandlin

No. 1

SEC. 5 T. 10 R. 22W
SW SW NW

Total Depth. 4140'
Comm. 7-30-57 Comp. 8-14-57
Shot or Treated.
Contractor. Transit Corporation
Issued. 10-19-57

County Graham
KANSAS



CASING:

8 5/8" 189' cem. w/135 sx

Elevation. 2360 KB

Production. Dry

Figures indicate Bottom of Formations.

surface sand & soil	189	
shale & shells	1485	
shale - red bed	1625	
sand iron	1725	
shale - red bed	1906	
anhydrite	1947	
shale	2140	
shale - lime	2655	
lime	2745	
lime & shale	3585	
lime	3661	
lime & shale	3730	
lime	3884	
lime & shale	3979	
shale-chert-lime	4020	
shale and chert	4064	
conglomerate	4098	
conglomerate - chert	4140	RTD
Total Depth		

TOPS:

Heebner	3596
Toronto	3619
Lansing	3632
Base of Kansas City	3859
Marmaton Chert	3944
Conglomerate	4025
Arbuckle	4126

D.S.T. #1 3658-3692 Open 1 hr. Rec.
405' SOC Muddy water. FP 0-180#. 15"
IBHSIP 1270#. 15" FBHSIP 1060#.

D.S.T. #2 3712-3742 Open 1 hr. Rec.
180' SW. FP 35-105#. 15" IBHSIP 1305#.
15" FBHSIP 1030#.

D.S.T. #3 3780-3820 Open 1 hr. Rec. 30'
VSOCM. FP 35-35#. 15" IBHSIP 195#. 15"
FBHSIP 55#.

D.S.T. #4 3817-3857 (Straddle Packers)
Open 1 hr. Rec. 40' mud. FP 30-35#. 15"
BHSIP 190#.