

Operator
 AMERICAN ENERGIES CORPORATION

DESIGNATE TYPE OF COMP.: OIL, GAS,
 DRY HOLE, SWDW, ETC.:
 Dry Hole

Well No. 1 Lease Name Stites - OWWO

S 7 T10S R 22 E W

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN,
 OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
@ 4077'. DST #1 4000' - 4077'. 30(30)60(60) Wk. blow throughout; Rec. 120' WCM, 200' Wtr. ISIP 1735#, FSIP , IFP 99-132#, FFP 154-164#. Temp. 110°. T.D. @ 4081' & plugging.				

Electric Log

Anhyd	1922(+459)	+5'
Heeb	3625(-1244)	+4'
Tor.	3647(-1266)	+4'
Lsg.	3663(-1282)	+4'
B/KC	3893(-1512)	+4'
Alt.	3932(-1551)	+4'
Paw. Ch.	3972(-1591)	+4'
Cgl.	4048(-1667)	+4'
Cgl. SS	4051(-1670)	+5'
Cgl. Ch.	4065(-1684)	+9'
LTD	4068(-1687)	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	President
	Title
	10-12-81
	Date

1705GL