

Operator
A. Scott Ritchie

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
oil

Well No. 2 Lease Name
Holquist-Holmes

s14 T10SR22 X
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

| FORMATION DESCRIPTION, CONTENTS, ETC. | TOP | BOTTOM | NAME | DEPTH |
|---|-----|--------|--------------|---------------|
| DST #1 3535'-3553' Wk blo increasing to fair. Rec. 40' ho&gcm; 135' mo; 15' mw. IFP 46-92#/30" FFP 92-115#/30"; IBHP 618#/45"; FBHP 607#/45". | | | | |
| DST #2 3571'-3595' Rec. 220' gas in pipe, 250' mgo, 180' cgo. IFP 46-161#/30"; FFP 161-207#/30" IBHP 392#/45"; FBHP 369#/45". | | | | |
| DST #3 3592'-3609' Wk blow 14". Rec. 60' vsoc thin mud. IFP 46-69#/30"; FFP 69-69#/30"; IBHP 819#/30"; FBHP 797#/30". | | | | |
| DST #4 3621'-3637' Fair blo. Rec. 240' gas in pipe, 75' cgo, 225' hocmw, 240' very socw. IFP 54-130#/30"; FFP 173-238#/60"; IBHP 934#/45"; FBHP 913#/45". | | | | |
| DST #5 3692'-3810' Fair blo. Rec. 2' vhocm, 120' ocm, 120' socm, 180' socmw. IFP 127-196#/30"; FFP 219-300#/60"; IBHP 1197#/45"; FBHP 1108#/45". | | | | |
| | | | ELECTRIC LOG | TOPS |
| | | | Anh | 1757' (+ 539) |
| | | | B/Anh | 1831' (+ 465) |
| | | | Top | 3290' (- 994) |
| | | | Heeb | 3506' (-1210) |
| | | | Tor | 3528' (-1232) |
| | | | Lans | 3533' (-1237) |
| | | | B/Kc | 3782' (-1486) |
| | | | LTD | 3810' (-1514) |

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

F. Hudson Higgs
Signature

Geologist

Title

March 29, 1978

Date