

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


15-065-00816

Company- WOODMAN & IANNITTI & FRANK A. OYSTER
Farm- Robinson No. 1

SEC. 18 T. 10 R. 22W
SE SE SW

Total Depth. 4108'
Comm. 12-29-58 Comp. 1-9-59
Shot or Treated.
Contractor. Woodman & Iannitti Drilg.
Issued. 4-25-59

County Graham
KANSAS



CASING:

8 5/8" 148' cem w/130 sx.
5 1/2" 4078' cem w/100 sx.

Elevation. 2360' RB

Production. 81 BOPD

Figures indicate Bottom of Formations.

sand & clay	40
clay	100
blue shale	148
shale	410
shale & sand	1645
sand, red bed	1894
Anhydrite	1940
shale, shells & salt	2135
shale & shells	2350
lime	2630
shale & lime	3125
lime	3430
lime & shale	3505
lime	3990
chert & lime	4108
Total Depth	

TOPS:

Anhydrite	1892
Topeka	3391
Heebner	3612
Toronto	3634
Lansing	3649
Base Kansas City	3873
Marmaton Chert	3961
Marmaton Sand	4031
Conglomerate	4073