

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


15-065-00572

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Dreiling "B" No. 1

SEC. 21 T. 10 R. 22W
NE NE NW

Total Depth. 3820'
Comm. 4-26-58 Comp. 5-7-58
Shot or Treated.
Contractor. Imperial Oil of Kans.
Issued. 6-28-58

County Graham
KANSAS



CASING:
8 5/8" 200' cem w/150 sx.

Elevation. 2335' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale & surface clay & sand	200
shale & shells	910
shale & sand	1040
shale & shells	1360
Dakota sand	1580
shale & shells	1660
shale, shells, anhydrite	2075
shale & shells	2280
shale & lime	3525
lime	3820 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1840
Heebner	3555
Toronto	3578
Lansing	3595

DST #1 3585-3610, op 2 hrs, rec. 570'
salt water, BHP 1060#.

DST #2 3620-41, op 2 hrs, rec. 1090'
salt water, BHP 1120#.

DST #3 3642-56, op 2 hrs, rec. 180' oil
cut salt water, 480' slightly oil cut
salt water (1% to 2% oil), BHP 1180#.

DST #4 3659-70, op 1 hr, rec. 15' mud
with specks of oil, BHP 60#.

DST #5 3667-84, op 2 hrs, rec. 240' salt
water, BHP 1170#.

DST #6 3716-40, op 1 hr, rec. 20' mud,
BHP 0#.

DST #7 3639-60, op 1 hr, rec. 20' mud
with specks oil, BHP 0#.

DST #8 3658-80, op 1 hr, rec. 10' mud,
BHP 0#.

DST #9 3676-3800, op 2 hrs, rec. 155'
salt water, BHP 1140#.