

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


15-065-00-175

Company- MURFIN-RAINS & WILLIAMSON  
Farm- Dreiling "E" No. 1

SEC. 30 T. 10 R. 22W  
NE NE NE

Total Depth. 4182'  
Comm. 10-2-58 Comp. 10-10-58  
Shot or Treated.  
Contractor. Murfin Drlg. Co.  
Issued. 11-22-58

County Graham  
KANSAS



Elevation. 2352' DE

Production. DRY

CASING:

8 5/8" 214' w/165 sx cem.

Figures indicate Bottom of Formations.

sand, shale	150
shale	760
sand, shale	830
shale, shells	895
sand	990
sand, pyrite	1010 ✓
sand	1045
shale, shells	1320
sand, shale	1565
and bed, shale	1870
Anhydrite	1910
shale, shells	2340
shale, lime, shells	2570
lime, shale	3686
lime	3764
lime, shale	3949
lime, shale, chert	4050
chert (Conglomerate)	4100
chert, shale	4138
lime, shale	4142
Arbuckle	4182
Total Depth	

TOPS: GEOL.

Anhydrite (scout)	1870
Heebner	3607
Toronto	3630
Lansing, Kansas City	3644
B/Kansas City	3872
Fort Scott	3960
Conglomerate	4044
Conglomerate Chert	4060
Simpson	4134
Arbuckle	4140