

Plotted Texas Co.

Company - J. J. LYNN
Farm - Webster

No. 1.

SEC. 34
NW 1/4 NE


T. 10

R. 22 W

Total Depth. 4101' PB 3627'
Comm. 9-18-43 Comp. 10-15-43
Shot or Treated. 1000 Gals. 10-13-43
Contractor. H.M. Williams Brlg. Co.
Issued. 12-25-43

County.

Graham
KANSAS



CASING:

10 3/4" 158'
5 1/2" 3618'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale & clay	40
shale	400
shale & shells	715
shale, shells, sand	1190
shale & shells	1780
anhydrite	1827
shale & shells	1835
shale, shells, red bed	2010
lime & shale	2120
shale & sdy lime	2320
lime & shale	2605
lime	2665
lime & shale	2920
lime	3000
lime & shale	3495
lime	3800
lime & shale	3840
conglomerate	3879
Miss. lime cherty	3891
lime brown cherty	3900
lime & shale	3935
lime, shale, chert	3990
lime	4101
Total Depth.	

Plugged back to 3627

Tops:

Anhydrite	1780
Topeka	3296
Lansing-K.C.	3542
Marmaton Formation	3802
Mississippi Lime	3872
Kinderhook Shale	3901
Maquoketa Shale	3927
Viola ? Lime Cherty	3975
Simpson Series	3990
Arbuckle	4050

sm sh oil (dead) 3564-70
lgt oil saturation 3614-17
good oil sh & sat. 3621-25
lgt oil show 3642-44, 3651-52
and 3653-55
better oil show 3659-60
good oil show 3663-65
traces of oil 3668-70 w/wtr
traces of dead oil 3761-65
dead oil in sand 3993, 3996,
and 4001-03
oil stains 4033-34, 4044-46,
and 4065-66