

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-03056

Company. HEATHMAN-SEELIGSON DRILLING CO.
Farm- Ray Stites No. 4

SEC. 1 T. 10 R. 23W
SW NE SE

Total Depth. 4067

Comm. 9-11-55


Comp. 9-21-55

County Graham
KANSAS

Shot or Treated.

Contractor. Heathman-Seeligson Drilling Co.

Issued. 11-12-55



CASING:

8 5/8 @ 169' w/ 125 sx cmt.

5 1/2 @ 3918' w/ 100 sx cmt.

Elevation. 2375 DF

Production. 378 BOPD-14% wtr.

Figures Indicate Bottom of Formations.

sand & shale	169
shale & shells	950
shale & sand	1295
shale & red bed	1455
sand	1675
shale & red bed	1934
anhydrite	1975
shale & shells	2255
lime & shale	2705
shale & broken lime	2800
lime & shale	3535
lime	3819
lime & shale	3992
lime, shale & chert	4067
Total Depth	

TOPS: (RB)

Anhydrite	1934
Heebner	3616
Lansing-KC	3650
Base K. C.	3872

DST #1: 3777-3800, open 2 hrs. rec.
95' muddy SW, w/ few specks oil,
BHP 1195#

DST #2: 3803-19, open 1 hr. rec. 10'
mud, BHP 0#.

Perf. 36/3819-29, show oil on gun
3822-25.

Acidized w/ 500 gals.