

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-005-00177

Company- HARRY GORE OIL CO.
Farm- Frank Law No. 1

SEC. 2 T. 10 R. 23W
NW NW SW

Total Depth. 4270
Comm. 6-13-51 Comp. 7-1-51
Shot or Treated.
Contractor. Strain Drlg.
Issued. 10-6-51

County Graham
KANSAS



CASING:
8 5/8" 178' cem. w/150 sx.
5 1/2" 4201 cem. w/175 sx.

Elevation. 2437 D.F.

Production. 77 bbls.

Figures Indicate Bottom of Formations.

sand & shale	45
shale blue	140
shale	950
sand, shale	1080
shale, shells	1290
shale	1525
sand	1555
sand & shale	1600
shale & shells	2005
anhyd.	2055
shale	2175
shale & shells	2355
lime & shale	2870
lime	2920
lime & shale	3440
lime	3490
lime & shale	3700
lime	3980
shale	4020
lime	4090
shale	4125
lime & sand	4141
lime & sand	4155
congl.	4190
lime & shale & chert	4210
chert	4240
congl.	4260
Arb.	4270
Total Depth Rotary bushing	

Tops:
Anhyd. 2005
Topeka 3477
Hoebner 3689
Dodge lime 3710
Lansing-K.C. 3720
Base K.C. 3953
Congl. 4046
Sand 4124-38
cherty congl. 4149
Arb. 4253

All meas. Rotary bushings.

D.S.T. 3789-3815 Tool open 1 hour rec.
540' slightly oil & gas cut muddy salt
wtr. BHP 15 min. 1150¹¹/₁₆ Flowing press 150¹¹/₁₆
D.S.T. 3902-3928 Tool open 1 hour rec.
10' oily mud BHP 15 min. -0. flowing press.
0.
D.S.T. 4126-4140 Tool open 1 hour rec. 240'
of very slightly mud cut oil. Slow study
blow. BHP 15 min. 1000¹¹/₁₆.

On 5 1/2" casing at 4201 R.B. corr. R.B.
to Braden Head 7'
Ran Schlumberger to T.D.