

✓
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-03058

Company- IMPERIAL OIL of KANSAS, INC.
Farm- Rice No. 1

SEC. 4 T. 10 R. 23W
NE SW SE

Total Depth. 4240'
Comm. 10-9-56 Comp. 11-6-56
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 12-22-56

County Graham
KANSAS



CASING:

8 5/8" 196' w/150 sx cem.
5" 4240'

Elevation. 2451' RB

Production. 28 BOPD, 67% wtr.

Figures indicate Bottom of Formations.

sand-clay	120
shale-shells	1180
sand-shale	1340
shale-red bed	1560
sand	1770
shale	1775
shale-sand-red bed	2025
Anhydrite	2060
shale-shells	2480
shale-lime	3747
lime	3990
Conglomerate	4240
Total Depth	

TOPS:

Anhydrite	2025
Heebner	3723
Toronto	3743
Lansing	3758
B/Kansas City	3982
Marmaton	4091
Cherty Conglomerate	4223

DST #1 - 3730-52 Open 1/2 hr.
Rec. 3' mud. BHP 650#. Toronto
should be further tested.

DST #2 - 3750-73 Open 1/2 hr. Red.
10' mud. BHP 180#. Zone judged
unworthy of further testing.

DST #3 - 3820-34 Open 1 hr. Rec.
1980' gas, 30' HOCM, 210' oil.
FP 60-100#, BHP 1060#.

DST #4 - 3904-22 Open 1/2 hr.
Rec. 10' mud w/slight show oil.
BHP 50#. 160' zone judged worthy of
further testing.

DST #5 - 3919-42 Open 1/2 hr.
Rec. 7' mud. BHP 0#. Zone judged
unworthy of further testing.