

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


5-005-00558

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Rice Estate No. 2

SEC. 4 T. 10 R. 23W
NW NW SE

Total Depth. 4010'
Comm. 6-21-58 Comp. 6-30-58
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 3-28-59

County Graham
KANSAS



Elevation. 2468' RB

Production. Dry

CASING:

8 5/8" 220' cem w/150 sx.

Figures indicate Bottom of Formations.

shale & sand	140
shale & shells	1245
shale, shells & sand	1905
shale & shells	2039
Anhydrite	2078
shale & shells	2415
lime & shale	3720
lime	4010 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Anhydrite	2039	
Heebner	3739	3742
Toronto	3760	3766
Lansing	3774	3778
Base Kansas City	3999	4000

DST #1 3838-51', op 2 hrs., rec. 240' gas,
60' oil cut mud, 36' heavy oil cut mud,
ICIP 545/20 mins., BHP 520#/20 mins.

DST #2 3852-65', packer failure.

DST #3 3855-65', op 1 hr., rec. 246'
salt water, BHP 1010#.

DST #4 3893-3979', op 1 hr., rec. 30'
drilling mud, BHP 50#.