

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-069-02287

Company- D. G. HANSEN
Farm- Gano No. 1

SEC. 6 T. 10 R. 23W
SE SE NW

Total Depth. 4043'
Comm. 8-23-57 Comp. 9-1-57
Shot or Treated.
Contractor. C-G Drilling Co.
Issued. 10-19-57

County Graham
KANSAS



CASING:

8 5/8" 203'

Elevation. 2452' DE

Production. Dry

Figures indicate Bottom of Formations.

All measurements taken from the top of rotary bushing.

surface soil	203
shale	750
shale-sand	1560
sand	1815
red bed	2064
anhydrite	2102
shale-lime	2165
lime-shale	4043
Total Depth	

TOPS:

anhydrite (scout)	2064
Topeka	3534
Heebner	3760
Toronto	3781
Lansing Kansas City	3797
Base Kansas City	4031

D.S.T. #1. 3820-45. Open 1 hr. Rec. 75'
VSOCM. IBHP-1438#. FBHP 1020#.

D.S.T. #2. 3917-50. Open 1/2 hr. Rec. 35'
mud & no oil. IBHP 1385#, BHP 1112#.

D.S.T. #3. 3944-67. Open 1 hr. 45 min.
Rec. 62' MOCM, 120' gas. IBHP-1453#.
FBHP-1178#.

D.S.T. #4. 3962-85. Open 40 min. Rec. 45'
mud, no oil. BHP 228#.