

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-01846

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Johnson "B" No. 2

SEC. 6 T. 10 R. 23W
NW NE SE

Total Depth. 3978'
Comm. 4-28-58 Comp. 5-6-58
Shot or Treated.
Contractor. Imperial Oil of Kans.
Issued. 8-1-58

County Graham
KANSAS



CASING:
8 5/8" 214' cem w/150 sx.
5 1/2" 3978' cem.

Elevation. 2423' RB

Production. 99 BOPD

Figures indicate Bottom of Formations.

surface sand & shale	214
shale, sand & shells	1050
iron & sand	1100
sand, shale & shells	1910
shale & shells	2031
Anhydrite	2070
shale & shells	2510
shale & lime	3745
lime	3978 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC LOG
Anhydrite	2031	
Heebner	3725	3725
Toronto	3747	3748
Lansing	3764	3762

DRILL STEM TESTS:

#1 3781-3802, op 1 hr, rec. 5' mud, BHP 0#.

#2 3823-38, op 2 hrs, rec. 360' gas, 30'
oil cut mud, 60' heavily oil cut mud, 1'
muddy salt water, BHP 1130#.

#3 3839-50, op 1 hr, rec. 30' salt watery
mud. BHP 1260#.

#4 3903-24, op 2 hrs, rec. 300' gas, 55'
oil cut mud, BHP 750#/30".

#5 3920-45, op 1 hr, rec. 10' mud, BHP 0#.