

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-03062

Company- PRIME DRILLING CO. & PETROLEUM MANAGEMENT
Farm- Dietz No. 2

SEC. 8 T. 10 R. 23W
C N/2 N/2 SW

Total Depth. 3995'
Comm. 12-6-57 Comp. 12-19-57
Shot or Treated.
Contractor. Prime Drlg. Co.
Issued. 5-17-58

County Graham
KANSAS



Elevation. 2413' KB

Production. 85 BOPD

CASING:

8 5/8" 258' cem w/175 sx.
5 1/2" 3994½' cem w/125 sx.

Figures indicate Bottom of Formations.

surface soil clay	85
sand	105
shale	260
shale & shell	1550
shale & sand	1760
red bed & shale	2000
Anhydrite	2040
shale & lime	2055
shale & shell	2300
shale & lime	2570
lime & shale	3462
lime	3995 RTD
Total Depth	

TOPS:

Heebner	3713
Toronto	3741
Lansing	3751

DRILL STEM TESTS:

- #1 3844-56, open 1½ hrs., rec. 190' salt water, ISIP 1190#, FSIP 1036#.
- #2 3898-3918, open 1½ hrs., weak blow increasing to a moderate blow at end of test. rec. 240' gas in pipe, 55' of oil cut mud, FSIP 141#, IFP 35#, FFP 40#.
- #3 3934-60, open 1½ hrs., weak blow increasing to a good blow at end of test, recovered 70' oil cut mud, FSIP 105#, IFP 45#, FFP 55#.