

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-01857

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Hoof "B" No. 5

SEC. 9 T. 10 R. 23W
C N/2 SW SW

Total Depth. 3886
Comm. 12-31-55 Comp. 1-19-56
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 8-18-56

County Graham
KANSAS



Elevation. 2412 RB

Production. 943 BOPD, NW

CASING:

8 5/8" 224' w/ 175 sx cmt.
5 1/2" 388_8 cmtd.

Figures indicate Bottom of Formations.

surface sand & shells	1045
hard sand & shale	1500
Dakota sand	1725
shale, shells & red bed	1975
anhydrite	2017
shale & shells	2575
shale & lime	3753
lime	3886
Total Depth	

TOPS:

Anhydrite	1975
Heebner	3658
Lansing	3696

DST #1: 3764-73, open 1/2 hr. rec. 5'
mud, BHP 0#.

DST #2: 3843-62, open 1 hr. gas to
surf. 1 hr. rec. 750' oil, FP 75-290#,
BHP 420#

DST #3: 3866-86, open 35 min. rec.
2100' gas, 350' oil, FP 50-145#,
BHP 440#/20 min.