

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02291

Company- BIRMINGHAM-BARTLETT DRLG. CO.
Farm- Johnson "E" No. 5

SEC. 9 T. 10 R.23W
NW SE SE

Total Depth. 3902
Comm. 3-6-55 Comp. 3-17-55
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg. Co.
Issued. 4-16-55

County Graham
KANSAS



Elevation. 2391 BB

Production. dry

CASING:

8 5/8" 239' ccm. w/175 sx

Figures indicate Bottom of Formations.

| | |
|----------------------|------|
| surface | 100 |
| shale & sand | 239 |
| shale, shells & sand | 1335 |
| shale & shells | 1435 |
| sand & shale | 1665 |
| shale & shells | 1925 |
| Anhydrite | 1955 |
| shale & shells | 2450 |
| broken lime | 2490 |
| lime & shale | 2705 |
| broken lime | 2795 |
| lime & shale | 2995 |
| broken lime | 3110 |
| shale & lime | 3394 |
| lime | 3405 |
| lime & shale | 3540 |
| broken lime | 3605 |
| shale & shells | 3615 |
| lime & shale | 3674 |
| lime | 3902 |
| Total depth | |

| | |
|-----------|------|
| Tops: | |
| Anhydrite | 1950 |
| Heebner | 3660 |
| Toronto | 3680 |
| Lansing | 3692 |

DST #1: 3660-96. Open 30 min., had weak blow that died in 8 min. recovered 8' mud. BHP 700#.

DST #2: 3700-21. Open 20 min., had weak blow that died in 3 min. recovered 6' mud. BHP 220#

DST #3: 3844-58. Open 25 min., had a weak blow that died in 6 min., recovered 6' mud. Shut-in pressure Off.

DST #4: 3866-77. Open 25 min., had a weak blow that died in 5 min., recovered 8' mud. Shut in pressure Off.

DST #5: 3858-3902. Open 30 min. had a weak blow that died in 10 min., recovered 15' mud.