

TYPE



AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

State Geological Survey

15-10-23W Compt.

(Rules 82-3-130 and 82-3-107)

WICHITA BRANCH

DOCKET NO. NP

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F Letter requesting confidentiality attached.

C Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)\*\*\*Check here if NO logs were run

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 6114 EXPIRATION DATE 6-30-84

OPERATOR Don E. Pratt Oil Operations API NO. 15-065-21,857

ADDRESS Box 370 Hays, KS 67601 COUNTY Graham FIELD

\*\* CONTACT PERSON Susie Ubert PHONE (913) 625-3446 PROD. FORMATION Lansing KC Indicate if new pay.

PURCHASER Clear Creek, Inc. LEASE C. Griffith

ADDRESS Century Plaza Building Wichita, KS WELL NO. 3-15 WELL LOCATION SW, SW, SE

DRILLING CONTRACTOR Murfin Drilling CO. ADDRESS 250, N. Water Suite 300 Wichita, KS 67202 440 Ft. from South Line and 2200 Ft. from East Line of the SE (Qtr.) SEC 15 TWP 10 RGE 23

PLUGGING CONTRACTOR ADDRESS

TOTAL DEPTH 4056 PBTD

SPUD DATE 9/8/83 DATE COMPLETED 9/16/83

ELEV: GR 2369 DF 2371 KB 2374

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 150' DV Tool Used?

WELL PLAT (Office Use Only) KCC KGS SWD/REP PLG. NGPA

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Table with 2 columns: Amount and kind of material used, Depth interval treated. Row 1: 3000 Gal- SGH-15%, 3792-98

Table with 4 columns: Date of first production, Producing method, Gravity, Disposition of gas treated. Row 1: 9/28/83, SWAB, Gravity, Production-L.P., 63 bbls., 65% 117 bbls., CFPB

76348

Side TWO  
OPERATOR Don E. Pratt

LEASE NAME 3-15 Griffith SEC 15 TWP 10 RGE23

(E)  
(W)

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<p>Check if no Drill Stem Tests Run. Check if samples sent Geological Survey.</p>				
Top Soil, Sand, Shale-----	224'		Topeka-----	-1014 = 3388
Shale & Sand-----	1435'		Heebner-----	-1242 = 3616
Sand (Cedar Hills)-----	1656'		Toronto-----	-1264 = 3638
Shale-----	1880'		Lansing KC----	-1280 = 3654
Shale (Red Bed)-----	1895'		Lansing KC Base-	-1504 = 387
Anhydrite-----	1933'		Marmaton-----	-1612 = 396
Shale-----	2140'		RTD-----	-1681 = 4055
Shale & Lime-----	3840'		LTD-----	-1682 = 4056
Lime-----	3880'			
Shale & Lime (RTD)-----	4055'			
DST #1--- 3646-95 Zones A, B REC: 65' mud 30-30 FP: 98-98 IBHP: 391		DST #4---3772-3840 REC: 372' OCM 30-30-60-30 IBHP: 887 FBHP: 742 FP: 49-166 176-196	Zones H, I, J	
DST #2---3678-3725 Zones C, D REC: 70' mud 30-30 IBHP: 303 FP: 29-98		DST #5---3836-80 REC: 4' mud with a few oil spots 30-30 BHP: 88 FP: 39-39	Zones K, L	
DST #3--- 3718-58 Zones E, F, G REC: 248' GAF 62'MO 310' OSM 248' MW 30-30-60-30 IBHP: 616 FBHP: 587 FP: 29-176 186-313				
If additional space is needed use Page 2				

Report of all strings set— surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Secks	Type and percent additives
Surface	12 1/2	8 5/8	20#	167'	CQS	110	
Prod String		4 1/2	10 1/2	4054'	CQS	200	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			4-SPE	SDJ	3792-98
Size 2 1/2 EUE	Setting depth 4025	Packer set at ----			

\*\* The person who can be reached by phone regarding any questions concerning this