

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01881

Company-SKELLY OIL CO.
Farm-Phy Stewart

No. 6

SEC. 16 T. 10 R.23W

NE SE SW

330' fr EL, 990' fr SL, SW/4

County Graham

KANSAS

Total Depth. 3910 PBSD 3857

Comm. 6-23-55


Comp. 7-5-55

Shot or Treated Acid.: 1250 gal. 3824-28, 1250 gal. 3808-14, 4500

Contractor. Claude Wentworth Drilling Co., Inc. gal. 3808-14. &

Issued. 9-10-55

3824-28



CASING:

8 5/8 @ 278' w/ 200 sx cmt.
5 1/2 @ 3889' w/ 200 sx cmt.

Elevation. 2377 DF

Production. 433 BOPD

Figures indicate Bottom of Formations

surface soil, sand, rock & shale	150
sand & rock	278
rock & shale	791
shale & shells	850
sandy lime & shale	1150
shale & lime	1480
shale & shells	1680
shale	1695
red bed & shale	1920
anhydrite	1960
lime & shale	2340
shale	2365
shale & lime	2660
lime	2720
lime & shale	3292
lime	3649
cherty lime	3659
lime	3744
chalky lime	3758
lime	3910
Total Depth	

TOPS:

Top Anhydrite	1919
Base Anhydrite	1955
Wellington	2254
Base Wellington	2450
Neva	2937
Near Topeka	3400
Heebner	3618
Toronto	3640
Lansing	3652

DST #1: 3727-39, open 30 min. strong blow thruout, rec. 90' VHO&GCM, 540' SW, IFP 30#, FFP 240#, BHP 1120#.

Producing formations: Lansing lime 3808-14 & 3824-28.