

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

15-065-03077


Company- IMPERIAL DRILLING CO., INC.
Farm- Brown "B" No.1

SEC. 20 T. 10 R. 23W
NE SW NE

Total Depth, 3935
Comm. 11-19-54 Comp. 11-30-54
Shot or Treated.
Contractor. Imperial Drilling Co., Inc.
Issued. 1-15-55

County Graham

KANSAS



CASING:
8 5/8 @ 220' w/ 150 sx cmt.
5 1/2 @ 3935' w/ 125 sx cmt.

Elevation. 2419 RB

Production. 1733 BOPD

Figures indicate Bottom of Formations.

surface sand & clay	165
shale & sand	630
shale, sand & shales	1140
shell & shells	1480
Dakota sand	1690
shale & shells	1966
anhydrite	2010
shale & shells	2685
shale & lime	3402
lime	3935
Total Depth	

TOPS:	
Anhydrite	1966
Heeoner	3657
Toronto	3677
Lansing-KC	3690

DST #1: 3844-60, open 1 hr. gas to surf. 55 min. rec. 806' oil, IFP 60#, FFP 300#, BHP 600#/15 min.

DST #2: 3864-81, open 45 min. gas to surf. 30 min. rec. 1172' oil, IFP 80#, FFP 383#, BHP 545#/20 min.

DST #3: 3876-98, open 45 min. weak blow air 10 min. & died. rec 15' rotary mud, FP 0#, BHP 55#/15 min.