


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. COLORADO OIL & GAS CORPORATION  
Farm. Griffith No. 2

SEC. 25 T. 10 R. 23W  
SE SE SE  
330' fr SL, 330' fr WL

Total Depth. 3808  
Comm. 8-5-55 Comp. 8-15-55  
Shot or Treated.  
Contractor. Glenn W. Peel  
Issued. 12-17-55

County Graham  
KANSAS



CASING:  
8 5/8 @ 193' w/ 175 sx cmt.

Elevation. 2302 DF

Production. Dry

Figures indicate Bottom of Formations.

surface clay	40
sand	90
shale	405
shale & shells	815
shale, shells & sand	1450
shale & shells	1803
anhydrite	1844
shale & shells	2190
lime & shale	2650
lime	2720
lime & shale	3000
lime & shale streaks	3100
shale & lime	3335
lime	3808
Total Depth	

Schlumberger TD 3807

TOPS:  
Heebner 3542  
Toronto 3565  
Lansing 3579  
Base K. C. 3804

All KB Meas.

DST #1: 3748-65, open 1½ hrs. fr. stdy.  
blow rec. 120' gas, 30' HO&GCM, 45'  
O&GCM, 45' salty muddy water, BHP  
1240#/30 min.

DST #2: 3775-3808, open 1½ hrs. fr.  
blow, rec, 423' SW, BHP 1220#/30 min.

Ran Schlumberger Laterolog Syrvey.