


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WALTERS DRILLING CO.
Farm- Walker No. 2

SEC. 20 T. 10 R.23W
SE SE NW

Total Depth. 4180
Comm. 1-18-56 Comp. 1-31-56
Shot or Treated. Perf. 32/3850-58, 2000 gals acid
Contractor. Walters Drilling Co.
Issued. 4-28-56

County Graham
KANSAS



Elevation. 2392 DF

Production. Dry

CASING:

8 5/8 @ 186' w/ 100 sx cmt.
5 1/2 @ 3927.49' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

surface	186
shale & shells	1530
sand	1709
shale & shells	1942
anhydrite	1984
shale & shells	2364
shale & lime	3713
lime	3997
lime & shale	4057
lime	4082
lime & shale	4180
Total Depth	

TOPS:

Anhydrite	1942
Heebner	3655
Toronto	3676
Lansing-K. C.	3690
Base K. C.	3925
Ft. Scott	4029
Cherokee sand zone	4128
Conglomerate	4159

Ran Lane-Wells log.

FU 325'/45 min. water & muddy water
700' wtr in hole/3 1/2 hrs w/ scum oil
1650' FIH w/ 150' oil on top.
Swbd. 18 BFPH/5 hrs. all water
Swbd 252 BW/7 hrs