

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- IMPERIAL OIL OF KANSAS, INCORPORATED
 Farm- Walker "A" No. 1

SEC. 20 T. 10 R. 23W
 NE SE NW

Total Depth. 3950'
 Comm. 8-30-56 Comp. 9-8-56
 Shot or Treated.

County Graham KANSAS

Contractor. Imperial Oil of Kansas, Incorporated
 Issued. 3-2-57



Elevation. 2410' RD

CASING:

8 5/8" 195' w/150 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

sand & clay	120
shale & shells	990
sand & shale	1245
sand	1304
shale & sand	1700
red bed & shale	1975
Anhydrite	2005
shale & Red Bed	2465
shale & lime	3620
lime	3950 RTD
Total Depth	

TOPS

Anhydrite	1975
Heebner	3681
Toronto	3700
Lansing	3716

DRILL STEM TEST

DST #1 3789-3804, op. 1 hr.
 Rec. 750' salt wtr.
 BHP 1300#.

DST #2 3849-91, op. 2 hr.
 Rec 150' muddy salt Wtr.
 FP 25-105#. BHP 910#.

DST #3, 3875-91, op 1/2 hr.
 Rec. 6' mud. BHP 0#.