

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-005-00581

Company- BURCH DRILLING COMPANY
Farm- Kerman No. 1

SEC. 35 T. 10 R. 23W
NW NW NE

Total Depth. 3800'
Comm. 8-26-58 Comp. 9-3-58
Shot or Treated.
Contractor. Burch Drilg. Co.
Issued. 1-3-59

County Graham
KANSAS



CASING:

8 5/8" @ 220' W/160 sx.
4 1/2" @ 3800'

Elevation. 2289' BB

Production. 85 BOPD

Figures indicate Bottom of Formations.

shale & shells	1150
shale	1806
anhydrite	1846
shale	2040
shale & lime	3548
lime	3800 RTD
Total Depth	

TOPS:

Anhydrite	1806
Heebner	3526
Toronto	3547
Lansing	3561
Base/K.C. (Scout)	3795

DST. #1. 3565-3575. Open 1 hr. Rec.
gas to surface in 40 min. plus 597'
slightly gas cut salt wtr. IBHP (30 min)
1010#, IFP 340#, FFP 400#, FBHP (30 min)
930#.

DST. #2. 3632-3660. Open 1 hr. Rec.
60' gas in drill pipe, plus 180' slight-
ly oil and gas cut mud plus 300' heavy
oil-gas cut mud, plus 95' salt wtr. IBHP
(30 min.) 1230#, IFP 110#, FFP 180#, FBHP
(30 min.) 930#.

DST. #3. 3648-3660. Open 1 hr. Rec.
150' slightly oil-gas muddy salt wtr.
plus 120' heavy oil gas cut muddy salt
wtr. plus 125' salt wtr.

DST. #4. 3717-3737. Open 1 hr. Rec.
2640' gas plus 695' oil. IBHP missed,
IFP 200#, FFP 245#, FBHP (30 min.) 530#.