

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.  
Farm- Diebolt No. 8

SEC. 33 T. 10 R. 23W  
NW SE NE

Total Depth. 3778

Comm. 8-10-55

Comp. 9-16-55


County Graham

KANSAS

Shot or Treated.

Contractor. Schafer Drilling Co.

Issued. 10-8-55



CASING:  
8 5/8 @ 220'  
5 1/2 @ 3778'

Elevation. 2350 RB

Production. 487 BOPD

Figures Indicate Bottom of Formations.

surface clay	40
shale	570
shale & shells	810
pyrite, sand & shells	950
shale & red bed	1350
sand & shale	1610
shale, shells & red bed	1845
anhydrite	1880
shale & shells	2290
shale & lime shells	2720
shale & lime	3535
lime	3778
Total Depth	

TOPS:	
Anhydrite	1845
Heebner	3544
Toronto	3563
Lansing	3582

DST #1: 3625-32, open 1 hr. rec. 3'  
mud, BHP 0#/20 min.

DST #2: 3655-65, open 1 hr. rec. 5'  
mud, BHP 0#/20 min.

DST #3: 3755-78, open 1 hr. gas to  
surf. 16 min. rec: 1455' gassy oil,  
IFP 80#, FFP 430#, BHP 1180#/20 min.