

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- STANOLIND OIL & GAS CO.
 Farm- M. P. Ott No. 1

SEC. 29 T. 10 R.23W
 NE NE NE
 330' S of NL, 330' W of EL

Total Depth. 3935 PSTD 3895
 Ccmm. 2-25-55 Comp. 3-31-55
 Shot or Treated.
 Contractor.
 Issued. 8-20-55

County Graham

KANSAS



Elevation. 2406 RB

Production. 3000 BOPD

CASING:

8 5/8 @ 197' w/ 150 sx cmt.
 5 1/2 @ 3930' w/ 650 sx cmt.

Figures Indicate Bottom of Formations.

sand	135
shale & shells	1950
anhydrite	1985
shale & shells	2410
lime & shale	3490
lime	3555
lime & shale	3675
lime	3855
lime, shale & conglomerate	3915
lime & shale	3935
Total Depth	

TOPS:

Heebner	3615
Lansing	3649

Perf. 3842-44w/ 4 SPF 2 hr tst. 26
 GOPH, NW, perf/ 3834-42 w/ 4 SPF, tst
 NW, top of fluid 1895. Perf. 3820-22
 w/ 4 SPF, top of fluid 1700, tr wtr,
 perf. 3814-20 w/ 4 SPF, swb approx.
 20 BOPH 1000' OB, swb approx. 13 1/2
 BOPH 1250' OB, FFU 2500' from top,
 @ noon, 2100' @ 2:30 PM, 2100' @ 4:30
 PM. Set HM tool @ 3830 acd. w/ 1000
 gal CP 15% type J acid. Acid displaced
 on vac. thru perf. 3814-22. held 150#
 press. on perf. 3834-44 thru tbg.
 Swbd. approx. 18 BOPH 2700' FT.
 11 BOPH 2450' FT