


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Mildred P. Ott No. 2

SEC. 29 T. 10 R. 23W
SW NE NE
990' N of SL, 990' W of EL

Total Depth. 4230 PBDT 3863
Comm. 7-22-55 Comp. 8-22-55
Shot or Treated.
Contractor.
Issued. 10-1-55

County Graham
KANSAS



CASING:
8 5/8 @ 204' w/ 150 sx cmt.
5 1/2 @ 3983' w/ 800 sx cmt.

Elevation. 2404 RB

Production. 2877 BOPD

Figures indicate Bottom of Formations.

surface clay & shells	85	Perf. 4/3823-28. swb 7 tstg 5 BNOPH
shale & shells	205	fr. btm. NW, ran tbg & packer set
shale	1100	@ 3834' Acid thru Perf. 3823-28,
shale & red bed	1770	1000 gal XF32 15%, displ. MP 100#
shale & shells	1946	time 12 min. Trtd down tbg thru
anhydrite	1985	perf. 3842-46 w/ 25 gal PRR 277 &
shale	2315	41 bbls crude, displ. 27 bbls mix.
lime & shale	3485	18 min. MP 900#m broke to 300#
lime	3904	Swb from btm. rec. load oil, Swb.
lime & shale	3992	20 BNOPH/6 hrs. NW.
lime	4037	
lime & shale	4096	Swb. & Tstg. thru perf. 3823-28,
lime	4150	3842-46, avg. 20 BNOPH, swb 2800'
lime & shale-cherty	4156	fr. surf. NW
Arbuckle	4230	
Total Depth		Plug back to 3863'

SCOUT TOPS:

Heebner	3627
Lansing	3660
Base KC	3902
Marmaton	3930
Arbuckle	4166

DST #1: 3660-70, open 1 hr. SI 20
min. rec. 200' muddy SW, no show,
VP 1290#, FFP 75#, BHP 1190#.

DST #2: 4167-75, open 30 min. SI 20
min. rec. 10' drlg. mud, VP 1125#,
IFP & FFP 0#, BHP 1080#.

Ran Electric logs.

Perf. 4/3879-82, tstg. 2 BNOPH, NW,
1000 gal XF32 acid thru perf. displ.
time 1 hr. 5 min. MP 250#, broke to
150#. Swb & rec. load oil & acid wtr.
3 hr. tstg. 20 BOPH. Swb. 1200' OB,
show oil, retainer set @ 3864', cmt.
135 sx thru perf, MP 3700#.

500 gal acid thru perf 3879-82, drl. out
cmt. 3854-90. Tstg 22 GOPH w/ tr.wtr.

500 gal XF 32 acid thru perf. 3879-82;
displ. time 5 hrs. MP 1400#, no break,
Swb. & rec. load oil & acid wtr. Swb.
from 3870', 1st hr. 20 BNO, 2nd. 18.33
BNO; 3rd. 15.03 BNO, 4th. 6.68, 5th.
.84, NW

Swb from 3870' 6th. hr. 1.67 BNO, 7th.
3.34 BNO, 8th. 3.34 BNO, 9th. 4.17 BNO
set plug @ 3873' capped w/ 1 gal Cal-Seal.
Cal Seal 3863', Perf 4/3842-46, Swb. from
btm. 6 hr. avg. 4 BNOPH,