

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- LARIO OIL & GAS
Farm- Nemechek No. 1

SEC. 28 T. 10 R. 23W
NW NE NW

Total Depth. 3905'
Comm. 6-25-54 Comp. 7-7-54
Shot or Treated.
Contractor. Transit Corp.
Issued. 8-28-54

County Graham

KANSAS



Elevation. 2390'

Production. Pmp. 85 B0/30% wtr.

CASING:

10 3/4" 245' w/175 sx. cem.
7" 3904' w/100 sx cem.

Figures Indicate Bottom of Formations.

sand-post rock	80
sand-shale	250
shale-shells	1350
red bed-sand	1410
sand	1680
shale-shells	1940
anhydrite	1974
shale-shells	2590
lime brkn	2700
brkn lime-shale	2795
shale-lime	3090
lime	3265
lime-shale	3336
lime	3905 RTD
Total Depth	

TCPS: R B	
Haebner	3615
T oronto	3631
Lansing	3647
Base Kansas City	3880

Perforated 4 holes per foot
3847-3852.

Acidized w/100 mud acid &
500 gals. plain acid.

Swabbed 4 BOPH for 4 hrs.

Acidized 1500 gals. etching
& swabbed 10 to 15 BOPH.

Perforated 20 holes 3829-3834.

Swabbed 10 BOPH natural.

Acidized 1000 gal. reg. 15%
acid.

Swabbed 10 BOPH.

Perforated 40 holes 3794-3804'
24 " 3814-3820'

Ran packer 3807 1/2-3824 1/2

Swabbed 7 1/2 BOPH

3000 gals. gel acid

Swabbed 10 BOPH for 4 hrs.

Put on pump.