

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- Cities Service Oil Co.  
Farm- Nemechek No. 2

SEC. 28 T. 10 R. 23W

NE SE SW

990' N & 330' W of  
S $\frac{1}{4}$  corner

County Graham  
KANSAS

Total Depth. 3862' PB 3842'

Comm. 4-17-55

Comp. 4-28-55

Shot or Treated.

Contractor. Lohmann-Johnson Drlg. Co., Inc.

Issued. 6-18-55

CASING:

8 5/8" 240' w/175 sx cem.

5 1/2" 3862' w/175 sx cem.

DV-tool @ 1900' w/600 sx cem. Figures indicate Bottom of Formations.

Elevation. 2375

Production. Phy. Pot. 483 BO  
& no wtr.

shale	305
shale-shells	1265
shale-sand	1830
shale-shells	1884
Anhydrite	1923
shale-shells	2340
lime-shale	3680
lime	3751
shale-lime	3870

3870-3862 SIM

Total Depth PB 3842

TOPS:

Corr. Topeka	3364
" Heebner	3580
" Dodge	3603
" Lansing	3616
" R/Kansas City	3844

Drilled cement to 3842 SIM

Perf. 42 shots 3778-89.

192' oil in 2 hrs.

402' oil in 4 hrs.

610' oil in 6 hrs.

797' oil in 14 hrs.

7 7/8" rotary hole.

