


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO.
 Farm- Nemechek No. 5

SEC. 28 T. 10 R. 23W
 SE NW NW

Total Depth. 3915
 Comm. 12-3-54 Comp. 12-13-54
 Shot or Treated.
 Contractor. Transit Corp.
 Issued. 2-12-55

County Graham
 KANSAS



Elevation. 2400 D.F.

Production. Phy. 227 BO & no wtr

Figures Indicate Bottom of Formations.

CASING:

8 5/8" 245' cem w/165 sx
 5 1/2" 3914' cem w/200 sx

clay	40
sand	70
shale, shells	1928
anhydrite	1971
shale, shells	2255
lime, shale	2442
lime brkn, shale	2600
lime, shale	2767
lime	2870
shale, lime	3319
lime	3337
lime, shale	3650
lime	3727
lime, shale	3787
lime	3899
lime, shale	3915
Total Depth	RTD

Tops: K.B. Meas.
 Topeka 3390
 Heebner 3616
 Toronto 3639
 Lansing-K.C. 3658
 Base Kansas City 3895

Perforated w/20 holes
 3854-3859
 Acidized with 2000 gals.