

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- CITIES SERVICE OIL COMPANY
 Farm- Nemechek No. 5

SEC. 28 T. 10 R. 23W
 NE NW SW
 330' S & 990' E of W/4 Corner

Total Depth. 3910' RTD 3898' CTTD
 Comm. 12-30-56 Comp. 1-8-57
 Shot or Treated.
 Contractor. Lohmann-Johnson Drlg. Co. Inc.
 Issued. 3-2-57

County Graham KANSAS



Elevation. 2379' DF

Production. 300 oil, no wtr.
 24 hrs. (Physical potential)

CASING:

8 5/8" 240' w/175 sx cem.
 5 1/2" 3907' w/200 sx cem.
 Stage collar 1908'
 w/130 bbls

Figures Indicate Bottom of Formations.

sand & shale	240
shale	815
shale & sand	1665
shale	1903
Anhydrite	1933
shale	1992
shale & shells	2265
shale	2640
lime	3042
lime & shale	3160
lime SLM 3908'	3910 RTD
PBTD	3898'

TOPS Dorr.
 Topeka 3404
 Heebner 3623
 Dodge 3649
 Lansing 3663
 Base/Kansas City 3888

PERFORATION

Perf. 57 shots 3836-50.
 71 gals. oil & 13 1/2 gals.
 muddy wtr. in 1 hr.
 1051' oil & 30' wtr.
 in 16 hrs.