


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO.
Farm- Nemechek No. 6

SEC. 28 T. 10 R. 23W
SE SE NW

Total Depth. 3880 PB 3830
Comm. 12-14-54 Comp. 12-23-54
Shot or Treated.
Contractor. Transit Corp.
Issued. 2-12-55

County Graham
KANSAS



Elevation. 2375 K.B.

Production. 35 bbls oil, 65 BWPD

Figures Indicate Bottom of Formations.

surface 240
shale 1364
shale, shells 1880
anhydrite 1925
shale, shells 2284
lime, shale 2510
lime broken 2675
lime, shale 3664
lime 3785
lime, shale 3807
lime 3842
lime, shale 3880
Total Depth PB 3830

Tops: K.B. Meas.
Heebner 3599
Toronto 3618
Lansing 3634
Base K.C. (Scout) 3871

Perforated 3838-45 w/4 holes
per ft.
Acidized w/300 gals.- Swabbed
1 1/2 to 2 Gal. oil per hr.,
some water
Acidized w/2500 gals.- no help.
Set plug at 3834', cem to 3830'
w/1 sx cem.
Perf. 3812-24'-w/4 holes per ft.
Acidized w/2500 gals. acid. Swabbed
2 bbls. fluid per hr w/some wtr.