


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- Steve Nemechek No. 7

SEC. 28 T. 10 R. 23W
C S/2. SE SE

Total Depth. 3865'
Comm. 4-21-56 Comp. 6-7-56
Shot or Treated.
Contractor. Brack Drlg.
Issued. 10-6-56

County Graham KANSAS



Elevation. 2348'

Production. 29 BO & 41 BWPD

CASING:

9 5/8" 2400' w/325 sx cem.
5 1/2" 23864' w/200 sx cem.

Figures indicate Bottom of Formations.

surf. soil, clay & sand	115
sand & gravel	145
shale & shells	401
shale & sand	850
sand	1060
shale, sand & shells	1154
sand & shells	1760
sand, shells & red bed	1860
lime & anhydrite	1900
shale & shells	2225
shells, shale & red bed	2380
shale, lime & red bed	2525
shale & red bed	2650
lime & shale	2710
lime	2790
lime & shale	3565
lime	3614
lime & shale	3705
lime #1,2	3805
lime & shale	3865
Total Depth	

TOPS:

Heebner	3560
Toronto	3580
Lansing/Kansas City	3593
Base/Lansing Kansas City	3825

DRILL STEM TESTS:

DST #1, 3748-65, op. 1 hr., 33 min. Weak blow for 10 min. Rec. 8' muddy wtr. FP I O#, F O#, BHP O#, SI 20 min.
DST #2, 3767-3805, op. 1 hr. weak blow for 4 min. Rec. 7' of watery mud. IFP O#, FFP O#, BHP O#, SI 20 min.