


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **MAGNOLIA PETROLEUM COMPANY**
 Farm- **Steve Nemechek** No. **8**

SEC. **28** T. **10** R. **23W**
 C **S 1/2** NE SE

Total Depth. **3880'**
 Comm. **10-25-56** Comp. **11-15-56**
 Shot or Treated.
 Contractor. **Brack Drilling Company**
 Issued. **2-2-57**

County **Graham** KANSAS *Dreholt*


Elevation. 2369'

Production. **State Potential**
124 BO & 6 BWPD

Figures indicate Bottom of Formations.

shale, lime	250
shale, shells,	
sand	930
shale, shells	1145
sand, shale	1610
shale, red bed	1815
Anhydrite,	
shale, red bed	2120
shale, red bed	2270
shale	2445
shale & red bed	2545
lime & shale	3370
lime	3420
lime & shale	3535
lime	3685
lime & shale	3751
lime	3880
Total Depth	

TOPS	
Heebner	3578
Toronto	3600
Lansing/Kansas	
City	3613
Base/Kansas	
City	3843

DRILL STEM TEST

DST #1 3768-86, op. 1 hr.
 gd blow, rec. 1200' GIP
 100' O & HGCM, 30' gsy
 mdy oil, 80' cln gsy oil.