


15-065-23238



TRILOBITE
TESTING, INC.

KCC
DEC 15 2006
CONFIDENTIAL

DRILL STEM TEST REPORT

Prepared For: **Coral Production Corporation**

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

13 10S 24W Graham KS

V. Gano #13-1

Start Date: 2006.11.24 @ 18:40:32

End Date: 2006.11.25 @ 03:45:32

Job Ticket #: 27404

DST #: 1

RECEIVED
DEC 20 2006
KCC WICHITA

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

Coral Production Corporation

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

V. Gano #13-1

13 10S 24W Graham KS

Job Ticket: 27404

DST#: 1

Test Start: 2006.11.24 @ 18:40:32

GENERAL INFORMATION:

Formation: **Lansing "C-D"**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 21:30:12

Time Test Ended: 03:45:32

Test Type: Conventional Bottom Hole

Tester: Tyson Flax

Unit No: 21

Interval: **3750.00 ft (KB) To 3850.00 ft (KB) (TVD)**

Total Depth: 3850.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2440.00 ft (KB)

2432.00 ft (CF)

KB to GRVCF: 8.00 ft

Serial #: 8289 Inside

Press@RunDepth: 211.61 psig @ 3757.00 ft (KB)

Start Date: 2006.11.24

End Date: 2006.11.25

Start Time: 18:40:37

End Time: 03:45:32


Capacity: 7000.00 psig

Last Calib.: 2006.11.25

Time On Btm: 2006.11.24 @ 21:29:32

Time Off Btm: 2006.11.25 @ 00:44:12

TEST COMMENT: IFP BOB in 16 min
ISI No blow back
FFP BOB in 20 min
FSI Weak surface blow back throughout



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1806.27	102.31	Initial Hydro-static
1	26.54	101.95	Open To Flow (1)
30	88.61	106.81	Shut-In(1)
76	941.88	111.16	End Shut-In(1)
77	118.02	110.97	Open To Flow(2)
135	211.61	116.22	Shut-In(2)
195	920.73	115.67	End Shut-In(2)
195	1696.77	116.11	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
15.00	FREE OIL	0.20
60.00	OCWM 10%O 10%W 80%M	0.81
180.00	SOCWM 10%O 30%W 60%M	2.42
120.00	MW w/scum of Oil 85%W 15%M	1.61

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27404

DST#: 1

ATTN: Rick Hall

Test Start: 2006.11.24 @ 18:40:32

Tool Information

Drill Pipe:	Length: 3738.00 ft	Diameter: 3.72 inches	Volume: 50.25 bbl	Tool Weight: 2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight set on Packer: 25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose: 62000.00 lb
		Total Volume: 50.25 bbl		Tool Chased 0.00 ft
Drill Pipe Above KB:	42.00 ft			String Weight: Initial 58000.00 lb
Depth to Top Packer:	3750.00 ft			Final 58000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	100.00 ft			
Tool Length:	154.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3697.00	
Shut In Tool	5.00			3702.00	
Telemetry tool	26.00			3728.00	
Hydraulic tool	5.00			3733.00	
Jars	5.00			3738.00	
Safety Joint	2.00			3740.00	
Packer	5.00			3745.00	54.00 Bottom Of Top Packer
Packer	5.00			3750.00	
Stubb	1.00			3751.00	
Perforations	5.00			3756.00	
Change Over Sub	1.00			3757.00	
Recorder	0.00	8289	Inside	3757.00	
Blank Spacing	64.00			3821.00	
Change Over Sub	1.00			3822.00	
Perforations	25.00			3847.00	
Recorder	0.00	3351	Inside	3847.00	
Bullnose	3.00			3850.00	100.00 Bottom Packers & Anchor
Total Tool Length:		154.00			



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

FLUID SUMMARY

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27404

DST#: 1

ATTN: Rick Hall

Test Start: 2006.11.24 @ 18:40:32

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 51.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.96 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2000.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
15.00	FREE OIL	0.202
60.00	OCWM 10%O 10%W 80%M	0.807
180.00	SOCWM 10%O 30%W 60%M	2.420
120.00	MW w/scum of Oil 85%W 15%M	1.613

Total Length: 375.00 ft

Total Volume: 5.042 bbl

Num Fluid Samples: 0


Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:





DRILL STEM TEST REPORT

Prepared For: **Coral Production Corporation**

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

13 10S 24W Graham KS

V. Gano #13-1

Start Date: 2006.11.25 @ 11:17:29

End Date: 2006.11.25 @ 18:36:59

Job Ticket #: 27405 DST #: 2

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Coral Production Corporation

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

V. Gano #13-1

13 10S 24W Graham KS

Job Ticket: 27405

DST#: 2

Test Start: 2006.11.25 @ 11:17:29

GENERAL INFORMATION:

Formation: **LKC "**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 12:50:09

Time Test Ended: 18:36:59

Test Type: Conventional Bottom Hole

Tester: Tyson Flax

Unit No: 21

Interval: **3855.00 ft (KB) To 3880.00 ft (KB) (TVD)**

Total Depth: 3880.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2440.00 ft (KB)

2432.00 ft (CF)

KB to GR/CF: 8.00 ft

Serial #: 8289

Inside

Press@RunDepth: 60.80 psig @ 3857.00 ft (KB)

Start Date: 2006.11.25

End Date:

2006.11.25

Start Time: 11:17:34

End Time:

18:36:58


Capacity: 7000.00 psig

Last Calib.: 2006.11.25

Time On Btm: 2006.11.25 @ 12:49:59

Time Off Btm: 2006.11.25 @ 16:34:28

TEST COMMENT: IFP BOB in 21.5 min
ISI Weak surface blow back throughout
FFP BOB in 15 min
FSI Weak surface blow back died in 50 min



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1892.21	101.28	Initial Hydro-static
1	17.13	100.66	Open To Flow (1)
32	32.93	105.61	Shut-In (1)
75	577.07	107.36	End Shut-In (1)
76	32.40	107.55	Open To Flow (2)
134	60.80	111.15	Shut-In (2)
225	581.41	112.49	End Shut-In (2)
225	1736.44	112.97	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
60.00	GMCO 30%G 50%O 20%M	0.81
60.00	GMCO 20%G 50%O 30%M	0.81

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

TOOL DIAGRAM

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27405

DST#:2

ATTN: Rick Hall

Test Start: 2006.11.25 @ 11:17:29

Tool Information

Drill Pipe:	Length: 3838.00 ft	Diameter: 3.72 inches	Volume: 51.59 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	64000.00 lb
		Total Volume:	51.59 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	11.00 ft			String Weight: Initial	58000.00 lb
Depth to Top Packer:	3855.00 ft			Final	60000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	25.00 ft				
Tool Length:	53.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3828.00	
Shut In Tool	5.00			3833.00	
Hydraulic tool	5.00			3838.00	
Jars	5.00			3843.00	
Safety Joint	2.00			3845.00	
Packer	5.00			3850.00	28.00 Bottom Of Top Packer
Packer	5.00			3855.00	
Stubb	1.00			3856.00	
Perforations	1.00			3857.00	
Recorder	0.00	8289	Inside	3857.00	
Perforations	20.00			3877.00	
Recorder	0.00	3351	Inside	3877.00	
Bullnose	3.00			3880.00	25.00 Bottom Packers & Anchor

Total Tool Length: 53.00



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

FLUID SUMMARY

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27405

DST#: 2

ATTN: Rick Hall

Test Start: 2006.11.25 @ 11:17:29

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 53.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.39 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2000.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
60.00	GMCO 30%G 50%O 20%M	0.807
60.00	GMCO 20%G 50%O 30%M	0.807

Total Length: 120.00 ft

Total Volume: 1.614 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

DST Test Number: 2


13 10S 24W Graham KS


Coral Production Corporation

Inside

Serial #: 8289

Pressure vs. Time





DRILL STEM TEST REPORT

Prepared For: **Coral Production Corporation**

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

13 10S 24W Graham KS

V. Gano #13-1

Start Date: 2006.11.26 @ 06:54:19

End Date: 2006.11.26 @ 15:50:38

Job Ticket #: 27406 DST #: 3

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Coral Production Corporation

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

V. Gano #13-1

13 10S 24W Graham KS

Job Ticket: 27406

DST#: 3

Test Start: 2006.11.26 @ 06:54:19

GENERAL INFORMATION:

Formation: **KC "H-J"**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 09:24:19

Time Test Ended: 15:50:38

Test Type: Conventional Bottom Hole

Tester: Tyson Flax

Unit No: 21

Interval: **3910.00 ft (KB) To 3973.00 ft (KB) (TVD)**

Total Depth: 3973.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2440.00 ft (KB)

2432.00 ft (CF)

KB to GR/CF: 8.00 ft

Serial #: 8289

Inside

Press@RunDepth: 506.78 psig @ 3918.00 ft (KB)

Start Date: 2006.11.25

End Date:

2006.11.25

Start Time: 06:54:24

End Time:

15:50:39


Capacity: 7000.00 psig

Last Calib.: 2006.11.26

Time On Btm: 2006.11.25 @ 09:24:09

Time Off Btm: 2006.11.25 @ 12:37:18

TEST COMMENT: IFP BOB in 1.5 min
ISI BOB in 6 min
FFP BOB immediately
FSI BOB in 5 min



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1931.31	103.75	Initial Hydro-static
1	78.02	102.98	Open To Flow (1)
29	228.25	120.39	Shut-In (1)
73	1276.46	118.46	End Shut-In (1)
73	251.73	118.06	Open To Flow (2)
134	506.78	119.72	Shut-In (2)
193	1248.63	120.81	End Shut-In (2)
194	1808.05	121.10	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
1050.00	GO 20%G 80%O	14.12
120.00	GMCO 20%G 60%O 20%M	1.61
120.00	GMCO 20%G 50%O 30%M	1.61
60.00	GHOCM 20% G 40%O 40%M	0.81
0.00	2550' GIP	0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27406

DST#: 3

ATTN: Rick Hall

Test Start: 2006.11.26 @ 06:54:19

Tool Information

Drill Pipe:	Length:	3901.00 ft	Diameter:	3.72 inches	Volume:	52.44 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight to Pull Loose:	64000.00 lb
					Total Volume:	52.44 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	19.00 ft							
Depth to Top Packer:	3910.00 ft							
Depth to Bottom Packer:	ft							
Interval between Packers:	63.00 ft							
Tool Length:	91.00 ft							
Number of Packers:	2		Diameter:	6.75 inches				
Tool Comments:								

Tool Description

Length (ft) Serial No. Position Depth (ft) Accum. Lengths

Change Over Sub	1.00			3883.00		
Shut In Tool	5.00			3888.00		
Hydraulic tool	5.00			3893.00		
Jars	5.00			3898.00		
Safety Joint	2.00			3900.00		
Packer	5.00			3905.00	28.00	Bottom Of Top Packer
Packer	5.00			3910.00		
Stubb	1.00			3911.00		
Perforations	6.00			3917.00		
Change Over Sub	1.00			3918.00		
Recorder	0.00	8289	Inside	3918.00		
Blank Spacing	31.00			3949.00		
Change Over Sub	1.00			3950.00		
Perforations	20.00			3970.00		
Recorder	0.00	3351	Inside	3970.00		
Bullnose	3.00			3973.00	63.00	Bottom Packers & Anchor

Total Tool Length: 91.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27406

DST#: 3

ATTN: Rick Hall

Test Start: 2006.11.26 @ 06:54:19

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

34 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 53.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.39 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3500.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
1050.00	GO 20%G 80%O	14.115
120.00	GMCO 20%G 60%O 20%M	1.613
120.00	GMCO 20%G 50%O 30%M	1.613
60.00	GHOCM 20% G 40%O 40%M	0.807
0.00	2550' GIP	0.000

Total Length: 1350.00 ft

Total Volume: 18.148 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:


Serial #: 8289


Inside

Coral Production Corporation

13 10S 24W Graham KS

DST Test Number: 3





DRILL STEM TEST REPORT

Prepared For: **Coral Production Corporation**

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

13 10S 24W Graham KS

V. Gano #13-1

Start Date: 2006.11.26 @ 06:54:19

End Date: 2006.11.26 @ 15:50:38

Job Ticket #: 27406 DST #: 3

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Coral Production Corporation

1600 Stout St Ste 1500
Denver CO 80202

ATTN: Rick Hall

V. Gano #13-1

13 10S 24W Graham KS

Job Ticket: 27497

DST#: 4

Test Start: 2006.11.27 @ 00:21:42

GENERAL INFORMATION:

Formation: **KC "K-L"**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 03:28:42

Time Test Ended: 08:10:32

Test Type: **Conventional Bottom Hole**

Tester: **Tyson Flax**

Unit No: **21**

Interval: **3975.00 ft (KB) To 4007.00 ft (KB) (TVD)**

Total Depth: **4007.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition: **Good**

Reference Elevations: **2440.00 ft (KB)**

2432.00 ft (CF)

KB to GR/CF: **8.00 ft**

Serial #: 8289 **Inside**

Press@RunDepth: **25.94 psig @ 3984.00 ft (KB)**

Start Date: **2006.11.26**

End Date: **2006.11.26**

Start Time: **00:21:47**

End Time: **08:10:32**

Capacity: **7000.00 psig**

Last Calib.: **2006.11.27**

Time On Btm: **2006.11.26 @ 03:28:22**


Time Off Btm: **2006.11.26 @ 05:29:11**

TEST COMMENT: **IFP Weak blow built to 1"**

ISI Weak surface blow back throughout

FFP Weak surface blow throughout

FSI No blow back



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1958.99	105.35	Initial Hydro-static
1	26.53	104.60	Open To Flow (1)
30	26.88	105.23	Shut-In(1)
61	39.27	106.17	End Shut-In(1)
61	29.60	106.18	Open To Flow (2)
91	25.94	107.20	Shut-In(2)
121	30.31	108.22	End Shut-In(2)
121	1880.65	108.93	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
2.50	VSOOM 5%O 95%M	0.03

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27497

DST#:4

ATTN: Rick Hall


Test Start: 2006.11.27 @ 00:21:42

Tool Information

Drill Pipe:	Length:	3963.00 ft	Diameter:	3.72 inches	Volume:	53.27 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	2.25 inches	Volume:	0.00 bbl	Weight to Pull Loose:	60000.00 lb
					Total Volume:	53.27 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	16.00 ft						String Weight: Initial	40000.00 lb
Depth to Top Packer:	3975.00 ft						Final	40000.00 lb
Depth to Bottom Packer:	ft							
Interval between Packers:	32.00 ft							
Tool Length:	60.00 ft							
Number of Packers:	2		Diameter:	6.75 inches				
Tool Comments:								

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3948.00	
Shut In Tool	5.00			3953.00	
Hydraulic tool	5.00			3958.00	
Jars	5.00			3963.00	
Safety Joint	2.00			3965.00	
Packer	5.00			3970.00	28.00 Bottom Of Top Packer
Packer	5.00			3975.00	
Stubb	1.00			3976.00	
Perforations	8.00			3984.00	
Recorder	0.00	8289	Inside	3984.00	
Perforations	20.00			4004.00	
Recorder	0.00	3351	Inside	4004.00	
Bullnose	3.00			4007.00	32.00 Bottom Packers & Anchor

Total Tool Length: 60.00



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Coral Production Corporation

V. Gano #13-1

1600 Stout St Ste 1500
Denver CO 80202

13 10S 24W Graham KS

Job Ticket: 27497

DST#: 4

ATTN: Rick Hall

Test Start: 2006.11.27 @ 00:21:42

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 10.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 55.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.39 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3500.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
2.50	VSOCM 5%O 95%M	0.034

Total Length:

2.50 ft

Total Volume:

0.034 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Pressure vs. Time

