

**KANSAS DRILLERS LOG**

*State Geological Survey*  
**WICHITA BRANCH**

S. 4 T. 10 R. 24 <sup>R</sup>/<sub>W</sub>

API No. 15 — 065 — 20,737  
County Number


Loc. SE SE SW

County Graham

Operator  
Don E. Pratt

640 Acres  
N

Address  
Box 370 Hays, Kansas 67601



Well No. #3 Lease Name Geo. Nickelson "B"

Locate well correctly  
Elev.: Gr. 2503

Footage Location SE SE SW  
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Murfin Drilling Co., Geologist J.R. Green

Spud Date 1-15-75 Total Depth 4110' P.B.T.D.

DF 2505 KB 2508

Date Completed 1-23-75 Oil Purchaser Charter

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/2 "	8 5/8	20#	208'	fast set	165 sks.	
oil string		4 1/2 "		4100'	common	150sks.	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
					3998' to 4004'

**TUBING RECORD**

Size	Setting depth	Packer set at
2"	4006'	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
1500 gas., acid.,	

**INITIAL PRODUCTION**

Date of first production		Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	<u>25</u> bbls.		<u>trace</u> MCF		
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.



4-10-24W

COMPANY Don E. Pratt

SEC. 4 T. 10S R. 24W

FARM Nickelson "B" NO. 3

LOC. App SE SE SW

15-065-20,737


RIG. NO. 15

TOTAL DEPTH 4110'

COUNTY Graham KANSAS

COMM. 1-15-75

COMP. 1-22-75



CONTRACTOR Murfin Drilling Company

CASING

20 10  
 15 5/8" @ 208' w/165 SX  
 12 6  
 13 5  
 4 1/2" @ 4100' w/150 SX

ELEVATION 2508 GL

PRODUCTION Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

160	Surface soil sand
208	Shale
875	Cement shale
1900	Shale & sand
2144	Shale - red bed
2183	Anhydrite
2890	Shale
3435	Shale & lime
4110	Lime
4110	TD

