

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- Imperial Oil Co.  
Farm- Dreiling "C" No. 2

SEC. 5 T. 10 R. 24W  
C SW NW

Total Depth. 4090'  
Comm. 7-19-62 Comp. 7-28-62  
Shot or Treated.  
Contractor. Imperial Oil of Kansas, Inc.  
Issued. 4-6-63

County Graham

KANSAS



Elevation. 2526' KB

**CASING:**

8 5/8" 183' cem w/150 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay & sand	183
shale	1510
shale & shells	1740
Dakota sand	1930
shale & red bed	2170
Anhydrite	2208
shale & shells	2350
lime & shale	3885
lime	4090 RTD
Total Depth	

**TOPS: SAMPLE**

Anhydrite	2170
Heebner	3816
Toronto	3840
Lansing	3850
Base Kansas City	4085

DST #1 3870'-3885' op 30 min. Very weak intermittent blow. rec. 15' mud, slightly oil specked. ICIP 1120#, IFP 8#, FFP 12#, FCIP 1065#/20 min.

DST #2 3889'-3905' op 30 min. Weak blow, died in 5 min. rec. 20' mud. ICIP 1122#, IFP 3#, FFP 36#, FCIP 1107#/20 min.

DST #3 3984'-4000' op 1 hr. Fair to good blow. rec. 60' VSO & GCMW, 90' SO & GCMW, 120' MW. ICIP 897#, IFP 52#, FFP 112#, FCIP 784#/20 min.

DST #4 4009'-4040' op 30 min. Very weak blow, died in 3 min. rec. 5' mud. ICIP 52#, IFP 18#, FFP 22#, FCIP 22#/20 min.

DST #5. 4039'-4060' op 30 min. Weak blow Died in 5 min. rec. 10' mud. ICIP 89# IFP 22#, FFP 30#, FCIP 37#/20 min.