

State Geological Survey

WICHITA BRANCH

W E L L L O G

15-065-20898

OPERATOR: LIBERTY ENTERPRISES, INC.

WELL NAME: GANO #3 LOCATION: NE SW NE 5-10-24W

COUNTY: GRAHAM STATE: KANSAS

WELL COMMENCED: 1/26/77 WELL COMPLETED: 2/3/77

ELEVATION: 2493' KB TOTAL DEPTH: 4005'

PRODUCTION: D & A RIG NO: 1

CASING - 8-5/8": 5 JTS, 194.85' WITH 140 SX CEMENT +2% GEL +3% CC.

5-1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1685	SHALE		
1685	1890	SAND		
1890	2130	RED BED & SAND		
2130	2167	ANHYDRITE		
2167	2220	RED BED		
2220	2630	SHALE & SHELLS		
2630	3870	LIME & SHALE		
3870	4005	LIME & RTD		

DST #1: 3846-3870 OP 30 SI 30 OP 60
SI 60. WEAK BLOW. REC 150' O&GCM,
1CHP 1148#, FBHP 1164#, IFP 55#,
FFP 113#.

DST #2: 3946-4005' OP 60 SI 30 OP 30
SI 30. WEAK BLOW. REC 90' VSOCM, 1BHP
178#, FBHP 178#, IFP 63#, FFP 103#.