

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- HONAKER-DAVIS DRIG. CO., ET AL
Farm- Schamberger No. 1

SEC. 16 T. 10 R. 24W
NW NW NW

Total Depth. 4070'
Comm. 5-22-56 Comp. 6-1-56
Shot or Treated.
Contractor. Honaker-Davis Drig. Co.
Issued. 7-14-56

County Graham

KANSAS



CASING:
8 5/8" 230' w/175 sx cem.

Elevation. 2478' RB

Production. Dry

Figures Indicate Bottom of Formations.

Top soil-Post rock	40
Post rock-gravel	150
Blue shale	700
red bed-shale	2000
shale-red bed	2152
Anhydrite	2190
shale-shells	2500
lime-shale	4036
lime	4037
lime-shale	4070 RTD
Total Depth	

TOPS:

Heebner	3783
Toronto	3805
Lansing-Kansas City	3818
B/Kansas City	4058

DST #1: 3815-3836 Tool open
30" - closed 30"
Weak blow 4"
Rec. 90' mud w/few
specks of oil.
Pressure: BHP 1370#.

DST #2: 3848-3868 Tool open
20" -closed 30"
Weak blow 5", Rec.
30' mud, Pressure
1370 #.

DST #3: 388-3910 Tool open
60" - closed 30",
Good blow, Rec. 435'
wtr. Pressure: BHP 1250#.
IFP 0#, FFP 200#.

DST #4: 3973-4001 Tool open
20" - closed 30",
weak blow 2", Rec.
10' mud, Pressure:
BHP 0#.

DST #5: Tool open 60", closed
30", good blow, Rec.
390' wtr. Pressure:
BHP 780#, IFP 60#, FFP 210#.