

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY DONALD C. SLAWSON

SEC. 19 T. 10 R. 24W
 LOC. NE NE NE

FARM Hobbs "A" NO. 2

TOTAL DEPTH 3942'
 COMM. 2-24-67 COMP. 3-5-67
 SHOT OR TREATED
 CONTRACTOR Leben Drlg.
 ISSUED 5-27-67

COUNTY Graham
 KANSAS



CASING
 20 10
 15 8 5/8" 248' cem w/ 175 sx
 12 6
 13 5
 4 1/2" 3940'

ELEVATION 2393' KB

PRODUCTION 93 BOPD, LANS
 3731-3837 Grav 38.40

FIGURES INDICATE BOTTOM OF FORMATIONS

0	90	Sand, Shale	TOPS! SCOUT	
90	900	Shale	Anhydrite	2020
900	1110	Shale, Sand	Topeka	3449
1110	2018	Shale, Shells	Heebner	3662
2018	2053	Anhydrite	Toronto	3686
2053	2080	Shale	Lansing	3704
2080	2496	Shale, Shells	Base Kansas	
2496	3130	Shale, Lime	City	3932
3130	3602	Lime, Shale		
3602	3940	Lime		
	<u>3940</u>	<u>RTD - Set 4 1/2" Casing</u>		
	3942	No Log		
		Total Depth		

8 5/8" 8 rd. 28# used surface casing set @ 248' cemented with 175 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Hobbs A-#2 Well, located NE NE NE of Section 19, Township 10 South, Range 24 West Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 7th day of March, 1967.

Wanda Russell