

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU--KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DON E PRATT

SEC. 20 T. 10 N. 24W
 LOC. NE SE NW

FARM D. Rush

NO. 1

TOTAL DEPTH 4013'

COMM. 12-16-66

COMP. 12-26-66


SHOT OR TREATED

CONTRACTOR L. J. Dreiling & Sons

ISSUED 4-1-67

COUNTY Graham

KANSAS



CASING

20
15
12
13

10
B 5/8" 187' cem w/ 150 sx

ELEVATION 2449' KB

4 1/2" 4010' cem w/ 150 sx

PRODUCTION 97 BOPD, NW
 Grav 33, Lans 3950-78

FIGURES INDICATE BOTTOM OF FORMATIONS

0'	187'	Top Soil - Post Rock
187'	415'	Shale
415'	1018'	Shale
1018'	1027'	Hard Sand
1027'	1493'	Shale & Sand Strks.
1493'	2060'	Shale & Red Bed
2060'	2075'	Anhy.
2075'	2104'	Anhy.
2104'	2335'	Shale
2335'	2441'	Shale & Shells
2441'	2600'	Shale & Lime
2600'	2800'	Lime & Shale
2800'	2925'	Shale & Lime
2925'	3145'	Lime & Shale
3145'	3300'	Lime & Shale
3300'	3465'	Lime & Shale
3465'	3600'	Lime & Shale
3600'	3640'	Lime & Shale
3640'	3758'	Lime
3758'	3791'	Lime
3791'	3814'	Lime
3814'	3830'	Lime
3830'	3865'	Lime
3865'	3870'	Lime
3870'	3916'	Lime
3916'	4010'	Lime RTD
4013'	Lime	Total Depth

TOPS: SCOUT

Anhydrite 2060

Heebner 3709

Toronto 3723

Lansing 3749

Base Kansas City 3984

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc, upon oath states
 that the above and foregoing is a true and correct copy from the Daily Drilling
 report from your D - Rush #1.