

CONTRACTOR'S WELL LOG

15-045-20863

OPERATOR:	Associates Oil & Gas, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	STRUSS #1
LOCATION:	C E/2 SE SW, Section 32-10S-24W
	Graham County, Kansas
SPUD DATE:	September 18, 1976
COMPLETION DATE:	September 27, 1976

0	180	Sand & Clay
180	990	Shale
990	1110	Sand
1110	1606	Shale
1606	1815	Sand
1815	2057	Shale & Sand
2057	2096	Anhydrite
2096	2300	Shale
2300	2642	Lime & Shale
2642	2820	Shale
2820	3400	Lime & Shale
3400	3508	Shale & Lime
3508	3626	Lime & Shale
3626	4025	Lime
	4025	Rotary Total Depth

Spud at 6:15 p.m. 9-18-76. Ran 6 jts. of 8 5/8" - 28# casing. Set at 252.57' with 160 sx. Common cement. Plug was down at 10:30 p.m. 9-18-76. (Cement Circulated)

Ran 121 jts. of 4 1/2" - 10 1/2# casing. Set at 4023' K.B. (overall tally 4059.05') Cemented with 175 sx. 60/40 posmix, salt saturated. Plug was down at 7:45 p.m. 9-27-76.

PLE TOPS:

Anhydrite 2057'
B/Anhydrite 2096'