

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- HONAKER-DAVIS DRIG. CO. ET AL  
Farm- Lichtsinn No. 1

SEC. 35 T. 10 R. 21W  
NE NE NE

Total Depth. 3942'  
Comm. 3-29-56 Comp. 4-7-56  
Shot or Treated.  
Contractor. Honaker-Davis Drig. Co.  
Issued. 5-26-56

County Graham

KANSAS



Elevation. 2337' RB

Production. Dry

CASING:

8 5/8" 254' cem w/150 sx

Figures indicate Bottom of Formations.

top soil & sand	20
sand & gravel	180
blue shale	255
shale	750
shale & shells	950
sand	1005
shale & shells	1315
red bed & shale	1490
sand	1695
shale & red bed	1950
lime & shale	3540
lime	3591
lime & shale	3790
lime	3813
lime & shale	3859
lime	3895
lime & shale	3942 RTD
Total Depth	

Tops:

Heepner	3664
Toronto	3684
Lansing-Kansas City	3698
Base Kansas City	3937

DST #1 3761-3813', tool open 15 mins., closed 20 mins.  
weak blow for 1/2 mins., rec. 25' mud BHP 1340#.

DST #2 3843-3895', tool open 15 mins., closed 20 mins.  
weak blow for 1/2 mins., rec. 15' mud BHP 140#.