

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

SEC. 4 T. 10 R. 25W
 LOC. C S/2 SE NE

COMPANY Beren Corporation
 970 Fourth Financial Center
 ROME NO. 1

COUNTY Graham
 KANSAS

TOTAL DEPTH 4310
 COMM. 4-23-79
 SHOT OR TREATED
 CONTRACTOR
 ISSUED

COMP. May 8, 1979

K. G. S. LIBRARY

CASING
 20 10
 15 B 5/8" 337/225sx,
 12 6
 13 F 4 1/2" 4225/200 SX

ELEVATION 2544 KB

PRODUCTION Oil Well
 Form & Invt
 NA

FIGURES INDICATE BOTTOM OF FORMATIONS

Well	Size	Production	Depth	Type	Seal	Fluids and Perfor. Additives
	8"	28	337'	60-40 po	225	3% CC, 2% gel
	4 1/2"	10.5	4225	60-40 poz	200	2% gel, 10% sa 3/4 of 1% CFR-

FORMATION DESCRIPTION	CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand		0	150		
Sand		150	180		
Shale		180	345		
Shale		345	560		
Shale and sand		560	1275		
Sand and shale		1275	1675		
Shale and sand		1675	2150		
Shale		2150	2187		
Anhydrite		2187	2223		
Shale		2223	2315		
Shale		2315	2540		
Shale and lime		2540	2635		
Shale		2635	2770		
Lime and shale		2770	2870		
Lime and shale		2870	3006		
Lime and shale		2906	3138		
Lime and shale		3138	3183		
Lime		3183	3243		
Lime		3243	3305		
Lime and shale		3305	3425		
Lime		3425	3515		
Lime		3515	3617		
Lime and shale		3617	3694		
Lime		3694	3775		
Shale and lime		3775	3839		
Lime		3839	3840		
Lime		3840	3845		
Lime		3845	3885		
Lime		3885	3935		
Lime		3935	3990		
Lime		3990	4000		
Lime		4000	4012		
Lime		4012	4054		
Lime		4054	4065		
Lime		4065	4120		
Lime		4120	4170		
Lime		4170	4195		
Lime and shale		4195	4225		
Lime and shale		4225			
T.D.					

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

6-50

BEREN CORPORATION 4-10-25W
 970 FOURTH FINANCIAL CTR #1 ROME C S/2 SE NE
 WICHITA, KS 67202
 CONTR HELBERG OIL CO. CTY GRAHAM
 GEOL ROBERT LEWELLYN FIELD ELRICK
 E 2544 KB CM 4/23/79 CARD ISSUED 6/27/80 IP OIL WELL
 FORM & INTV NA

+	+	+
+	+	+
+	+	+

API 15-065-21,108

LOG	TOPS	DEPTH	DATUM
ANH		2184	+ 360
B ANH		2220	+ 324
HEEB		3784	-1240
TOR		3808	-1264
LANS		3828	-1284
BKC		4051	-1507
PAW		4184	-1640
CHER LM		4260	-1716
LTD		4277	-1733
E RTD		4310	-1766

8-5/8" 337/225sx, 4 1/2" 4225/200sx
 DST (1) 3813-3840 (A)/30-30-30-75,
 REC 20' M, SIP 544-544#, FP 21-21/
 21-21#
 DST (2) 3930-3990 (H-I)/30-45-60-60, RE-
 120' G, 20' HOOCM, 60' OCMW, 60'
 SOCMW, 180' WTR, SIP 731-648#, FP
 42-105/105-199#
 DST (3) 3984-4012 (J)/30-45-60-60, REC
 240' G, 360' VHOOCM, 120' OCM,
 120' VSOCM, SIP 1012-960#, FP 63-
 262/262-324#
 DST (4) 4008-4065 (K-L)/30-45-120-60,
 REC 20' SOCM, 180' MDY WTR, SIP
 366-356#. FP 42-73/84-136#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)

BEREN CORPORATION #1 ROME 4-10-25W
 C S/2 SE NE

DST (5) 4265-4280 (CHER LM)/45-45-45-45
 REC 60' CL O, 60' VHOOCM, 20' HOOCM,
 SIP 1220-1146#, FP 21-42/42-84#
 MICT - CO, TSTD - (FORM & INTV NA) -
 POP, P 16 BOPD, NO OTHER INFO TO BE
 RELEASED AT PRESENT - WILL RELEASE
 INFO WHEN AVAILABLE