


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **MAGNOLIA PETROLEUM CO.**
 Farm- **Elmer E. Fox** No. **1**

SEC. **3** T. **10** R. **25W**
 SW SW SE

Total Depth. **4235'**
 Comm. **3-9-59** Comp. **3-22-59**
 Shot or Treated.
 Contractor. **Peel Brothers**
 Issued. **6-6-59**

County **Graham**
KANSAS



Elevation. **2491'**

Production. **Dry**

Figures indicate Bottom of Formations.

clay & sand	180
blue shale	238
shale & shells	535
shale	1100
sand & shale	1300
shale	1725
shale & red bed	2145
shale	2160
Anhydrite	2195
red bed & shale	2295
shale & shells	2405
shale & lime strks	2530
shale & brkn lime strks	2780
lime	2905
lime & shale	3015
lime	3220
lime & shale	3410
lime	3600
lime & shale	3700
lime	4005
lime & shale	4030
Conglomerate	4125
lime & shale	4217
lime	4235
Total Depth	

TOPS:

Heebner	3741
Toronto	3764
Lensing-Kansas City	4016
Cherokee Shale	4208
Cherokee Limestone	4216

DST #1 3913-3933', op 1 hr., wk bl to surf.
 IFP 21#, FFP 18-21#, ISIP 47#, FSIP 26#/
 30 min. IHH 2093#, FHH 2093#; rec. 10' DM.

DST #2 4220-4235', op 1 hr, rec. 12' oil
 speckled mud. IFP 21#, FFP 21', ISIP 307#
 FSIP 50#/30 mins. IHH 2319#, FHH 2312#.